

SUMMARY OF QUANTITIES

SPECIAL PROVISION SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75%	
					CITY = 25%	
					ROADWAY	BRIDGE REHABILITATION
					0004	0014
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,198	3,198	
	40600300	AGGREGATE (PRIME COAT)	TON	68	68	
Δ	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,080	1,080	
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	500	500	
	40600990	TEMPORARY RAMP	SQ YD	200	200	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,888	1,888	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,492	3,492	
	42400800	DETECTABLE WARNINGS	SQ FT	1,584	1,584	
	44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	19,240	19,240	
	44000600	SIDEWALK REMOVAL	SQ FT	3,492	3,492	
	44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	4	4	
	44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	32	32	
	44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	32	32	
	44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	123	123	
*	58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	3,110		3,110
Δ	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1	
Δ	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	43	43	
	67100100	MOBILIZATION	L SUM	1	1	
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	

SPECIAL PROVISION SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75%	
					CITY = 25%	
					ROADWAY	BRIDGE REHABILITATION
					0004	0014
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	5	5	
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	3,840	3,840	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,280	1,280	
	72000100	SIGN PANEL TYPE I	SQ FT	9	9	
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	16	16	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	999	999	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,420	4,420	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,428	5,428	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	795	795	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	670	670	
Δ *	88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,860	2,860	
Δ	X6024503	INLETS TO BE ADJUSTED WITH NEW FRAME AND GRATE (SPECIAL)	EACH	5	5	
Δ	X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	11	11	
Δ	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	44	44	
Δ *	XZ006305	BRIDGE DECK WEARING SURFACE	SQ YD	3,110		3,110
Δ *	Z0003700	BEARING PAD ADJUSTMENT	EACH	220		220
Δ *	Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	3,110		3,110
Δ	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	323	323	
Δ *	Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	200		200
Δ	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	129	129	
Δ *	Z0032700	KEYWAY REPAIR	FOOT	3,375		3,375
Δ	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	1

Δ SEE SPECIAL PROVISIONS
* SPECIALTY ITEMS

Plotted: February 15, 2012 @ 3:02 PM By: Kris Pung - Tab: 03 Quantities - 22x34

COPYRIGHT © 2012 ENGINEERING ENTERPRISES, INC.

USER NAME =	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE =	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. N/A TO STA. N/A

F.A.U. RTE. 1314	SECTION 11-00182-00-RS	COUNTY KANE	TOTAL SHEETS 25	SHEET NO. 3
CONTRACT NO. 63689				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT NO. M-9003(B47)				

Path: \\SUSARPC01\EG1005\DWG\FINAL_ENG\EG1005-CR