


LEGEND

- EXISTING SIDEWALK
- CLASS D PATCHES
- HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
- CURB & GUTTER REMOVAL AND REPLACEMENT & SIDEWALK REMOVAL AND REPLACEMENT
- EXISTING BRICK PAVERS
- FRAMES & LIDS TO BE ADJUSTED (SPECIAL)
- SANITARY MANHOLE TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID
- INLET TO BE ADJUSTED WITH NEW FRAME AND GRATE (SPECIAL)
- TEMPORARY RAMP TO BE CONSTRUCTED AT HANDHOLE/UTILITY STRUCTURE UNLESS OTHERWISE NOTED (NO ADJUSTMENT)



- NOTES:**
- ALL STRUCTURES WITH FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) SHALL BE REPLACED WITH A NEW CLOSED FRAME AND LID (FRAMES AND LIDS, TYPE 1, CLOSED LID TO BE PAID FOR SEPARATELY).

COPYRIGHT © 2012 ENGINEERING ENTERPRISES, INC.

USER NAME =	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE =	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PLAN, CONSTRUCTION NOTES
AND DETAILS**

SCALE: 1"=20' SHEET NO. 3 OF 4 SHEETS STA. 86+50 TO STA. 96+50

F.A.U. RTE. 1314	SECTION 11-00182-00-RS	COUNTY KANE	TOTAL SHEETS 25	SHEET NO. 10
FED. ROAD DIST. NO. 1 [ILLINOIS]			CONTRACT NO. 63689	
FED. AID PROJECT NO. M-9003(847)				

Plotted: January 26, 2012 @ 7:44 AM By: Kris Pung - Tab: 10 Plan - 22x34

P:\FHWA\525\KPROVA\EG1003\DWG\FINAL\ENG\EG1003-PLAN