



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

1. MILL HMA FIRST IF THERE IS AT LEAST 4 1/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

COPYRIGHT © 2012 ENGINEERING ENTERPRISES, INC.			
FILE NAME =	USER NAME = bboardl	DESIGNED - R. SHAH	REVISED - A. ABBAS 04-27-98
c:\projects\dstata22x34\bd22.dgn		DRAWN -	REVISED - R. BORO 01-01-07
PLOT SCALE = 80.000' / 1" IN.		CHECKED -	REVISED - R. BORO 09-04-07
PLOT DATE = 10/27/2008		DATE - 10-25-94	REVISED - K. ENG 10-27-08

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PAVEMENT PATCHING FOR
HMA SURFACED PAVEMENT**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1914	11-00162-00-BS	KANE	25	22
BD400-04 (BD-22)			CONTRACT NO. 63689	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Plotted: January 19, 2012 @ 4:13 PM By: Leah Boatman - Job: 22 BD-22 22x34

Path: H:\S\SR\PROJ\EGT005\DWG\DMG_FINAL_ENG\EGT005-CVR