

DATE	
BY	
SURVEYED	
REVISIONS	
TEMP. DATE	
AREAS	
CHECKED	
NO.	

DATE	
BY	
SURVEYED	
REVISIONS	
TEMP. DATE	
AREAS	
CHECKED	
NO.	

SUMMARY OF QUANTITIES			URBAN	0014 BRIDGE REPAIR
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	143	143
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	86	86
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	870	870
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1273	1273
50102400	CONCRETE REMOVAL	CU YD	13.8	13.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	13.6	13.6
50300260	BRIDGE DECK GROOVING	SQ YD	730	730
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	980	980
50800515	BAR SPLICERS	EACH	24	24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	163	163
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2985	2985
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2	2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1697	1697
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14835	14835
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4945	4945
70400100	TEMPORARY CONCRETE BARRIER	FOOT	700	700
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	700	700
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3490	3490
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1378	1378
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	276	276
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3
* 78100300	REPLACEMENT REFLECTOR	EACH	69	69
78200410	GUARDRAIL MARKERS, TYPE A	EACH	25	25
78200520	BARRIER WALL MARKERS, TYPE B	EACH	20	20
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2036	2036
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3
Z0006014	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	784	784
Z0012144	BRIDGE DECK SCARIFICATION 2 1/2"	SQ YD	784	784

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN	0014 BRIDGE REPAIR
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	10	10
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	10	10
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

FILE NAME = 0264H21-shr-S00.dgn
 PLOT DATE = 1/23/2012
 PLOT SCALE = 50.0000' / 1" IN.



DESIGNED - G.F.L./K.R.K. REVISIONS -
 DRAWN - K.R.K. REVISIONS -
 CHECKED - E.J.M. REVISIONS -
 DATE - DECEMBER 2011 REVISIONS -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL 251 AT DRY RUN CREEK

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
738	(5B)M	WINNEBAGO	24	3
			CONTRACT NO. 64H21	