

# SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50						40603310
			WIDTH	SQYD	INCHES	TONS
Stage 1						
SB	176+55.00	179+90.00	4	148.9	2	16.7
SB	181+15.00	185+25.00	4	182.2	2	20.4
NB	175+50.00	179+65.00	4	184.4	2	20.7
NB	180+90.00	184+25.00	4	148.9	2	16.7
Stage 2						
SB	176+55.00	179+40.00	4	126.7	2	14.2
SB	181+75.00	185+25.00	4	155.6	2	17.4
NB	175+50.00	179+00.00	4	155.6	2	17.4
NB	180+40.00	184+25.00	4	171.1	2	19.2
TOTAL				1273.3		142.6

HOT-MIX ASPHALT SURFACE REMOVAL, 2"				44000157
			WIDTH	SQ YD
Stage 1				
SB	176+55.00	179+90.00	4	148.9
SB	181+15.00	185+25.00	4	182.2
NB	175+50.00	179+65.00	4	184.4
NB	180+90.00	184+25.00	4	148.9
Stage 2				
SB	176+55.00	179+40.00	4	126.7
SB	181+75.00	185+25.00	4	155.6
NB	175+50.00	179+00.00	4	155.6
NB	180+40.00	184+25.00	4	171.1
TOTAL				1273.3

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70				40603340	
			SQYD	INCHES	TONS
SB SOUTH APPROACH					
			201.0	1.75	19.7
SB NORTH APPROACH					
			237.0	1.75	23.2
NB SOUTH APPROACH					
			230.0	1.75	22.5
NB NORTH APPROACH					
			202.0	1.75	19.8
TOTAL				870	85.3

HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"				44000156
			SQ YD	
SB SOUTH APPROACH				
			201	
SB NORTH APPROACH				
			237.0	
NB SOUTH APPROACH				
			230.0	
NB NORTH APPROACH				
			202.0	
TOTAL				870

SHORT TERM PAVEMENT MARKING			70300100
			FOOT
SOUTHBOUND			
SKIP-DASH	149+00.00	184+75.00	295
YELLOW	176+55.00	185+25.00	287
WHITE	176+55.00	185+25.00	287
	161+45.00	162+83.00	46
	161+45.00	162+83.00	46
NORTHBOUND			
SKIP-DASH	176+00.00	195+35.00	160
YELLOW	175+50.00	184+25.00	289
WHITE	175+50.00	184+25.00	289
TOTAL			1697

TEMPORARY PAVEMENT MARKING - LINE 4"				70300220	
			FOOT	FOOT	
STAGE 1					
				YELLOW	WHITE
SOUTHBOUND					
	149+00.00	162+45.00		1345	
	161+50.00	162+45.00		95	
	161+50.00	185+25.00		2375	
	175+50.00	185+25.00	975		
NORTH BOUND					
	176+00.00	195+35.00		1935	
	175+50.00	184+25.00	875		
STAGE 2					
SOUTHBOUND					
	149+00.00	184+75.00	3,575		
	176+75.00	185+25.00		850	
NORTH BOUND					
	176+00.00	195+35.00	1,935		
	175+50.00	184+25.00		875	
				7,360	7,475
TOTAL				14,835	

WORK ZONE PAVEMENT MARKING REMOVAL				70301000	
			YELLOW	WHITE	
STAGE 1					
SOUTHBOUND					
	149+00.00	162+45.00		1345	
	161+50.00	162+45.00		95	
	161+50.00	185+25.00		2375	
	175+50.00	185+25.00	975		
NORTH BOUND					
	176+00.00	195+35.00		1935	
	175+50.00	184+25.00	875		
STAGE 2					
SOUTHBOUND					
	149+00.00	184+75.00	3,575		
	176+75.00	185+25.00		850	
NORTH BOUND					
	176+00.00	195+35.00	1,935		
	175+50.00	184+25.00		875	
				7,360	7,475
TOTAL				14,835	
TOTAL SQ FT				4945	

TEMPORARY CONCRETE BARRIER			70400100	
			FOOT	
STAGE 1				
	178+34.56	181+88.11	350	
	178+96.39	182+50.82	350	
TOTAL				700

RELOCATE TEMPORARY CONCRETE BARRIER			70400200	
			FOOT	
STAGE 2				
	178+34.46	181+88.07	350	
	178+96.34	182+50.82	350	
TOTAL				700

BARRIER WALL MARKERS, TYPE B				78200520
			25' SPACING	TOTAL
SOUTH BOUND				
	179+90.00	181+10.00	/25	5
	180+05.00	181+30.00		5
NORTH BOUND				
	179+55.00	180+75.00		5
	179+70.00	180+90.00		5
TOTAL				20

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)				78100105
				EACH
Stage 1				
SB	180+04.00	181+25.00		1.5
SB	179+55.00	180+75.00		1.5
TOTAL				3

REPLACEMENT REFLECTOR				78100300
				EACH
SOUTHBOUND				
SKIP-DASH	165+45.00	184+75.00	45	45
NORTHBOUND				
SKIP-DASH	176+00.00	195+35.00	24	24
TOTAL				69

GUARDRAIL MARKERS, TYPE A				78200410
			25' SPACING	TOTAL
SOUTH BOUND				
	176+95.00	179+90.00	/25	12
	178+25.00	180+05.00		7
NORTH BOUND				
	180+75.00	182+35.00		6
	181+90.00	183+80.00		8
TOTAL				25

SHOULDER RUMBLE STRIPS, 16 INCH				64200116
				SQYD
MEDIAN SHOULDERS				
Stage 1				
SB	176+55.00	179+90.00		335
SB	181+10.00	185+25.00		415
NB	175+50.00	179+65.00		415
NB	180+90.00	184+25.00		335
OUTSIDE SHOULDERS				
Stage 2				
SB	176+55.00	180+00.00		345
SB	181+30.00	185+25.00		395
NB	175+50.00	179+50.00		400
NB	180+80.00	184+25.00		345
TOTAL				2985

PAVEMENT MARKING REMOVAL						78300100
				INCH		SQ FT
SOUTHBOUND						
SKIP-DASH	149+00.00	184+75.00	894	6		446.88
YELLOW	176+55.00	185+25.00	870	4		290.00
WHITE	176+55.00	185+25.00	870	4		290.00
	161+45.00	162+83.00	138	8		92.00
	161+45.00	162+83.00	138	8		92.00
NORTHBOUND						
SKIP-DASH	176+00.00	195+35.00	484	6		241.88
YELLOW	175+50.00	184+25.00	875	4		291.67
WHITE	175+50.00	184+25.00	875	4		291.67
TOTAL						2036.1

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3				Z0030250
				EACH
STAGE I				
	178+34.56			1
	182+50.82			1
TOTAL				2

IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3				Z0030350
				EACH
STAGE II				
	178+34.46			1
	182+50.82			1
TOTAL				2

THERMOPLASTIC PAVEMENT MARKING - LINE 4"				78000200
SOUTHBOUND				
YELLOW	176+55.00	185+25.00		870
WHITE	176+55.00	185+25.00		870
NORTHBOUND				
YELLOW	175+50.00	184+25.00		875
WHITE	175+50.00	184+25.00		875
TOTAL				3,490

THERMOPLASTIC PAVEMENT MARKING - LINE 6"				78000400
SOUTHBOUND				
SKIP-DASH	149+00.00	184+75.00		894
NORTHBOUND				
SKIP-DASH	176+00.00	195+35.00		484
TOTAL				1,378

THERMOPLASTIC PAVEMENT MARKING - LINE 8"				78000500
SOUTHBOUND				
	161+45.00	162+83.00		138
	161+45.00	162+83.00		138
TOTAL				276

DATE	BY	DATE
DATE	BY	DATE
DATE	BY	DATE
DATE	BY	DATE
DATE	BY	DATE

DATE	BY	DATE
DATE	BY	DATE
DATE	BY	DATE
DATE	BY	DATE
DATE	BY	DATE

FILE NAME =D264H21-sht-sched1.ejgdn  
 PLOT DATE =1/24/2012  
 PLOT SCALE=50.0000' / 1" IN.

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - G.F.L./K.R.K.  
 DRAWN - K.R.K.  
 CHECKED - E.J.M.  
 DATE - DECEMBER 2011  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES - IL 251 AT DRY RUN CREEK**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 738	SECTION (5B)M	COUNTY WINNEBAGO	TOTAL SHEETS 24	SHEET NO. 4
ILLINOIS			CONTRACT NO. 64H21	