

DATE	
BY	
FINAL SURVEY	
SURVEYED	
PLOTTED	
DATE	
AREAS	
AREAS CHECKED	
NO.	

DATE	
BY	
ORIGINAL SURVEY	
SURVEYED	
PLOTTED	
DATE	
AREAS	
AREAS CHECKED	
NO.	

SUMMARY OF QUANTITIES			URBAN	0014 BRIDGE REPAIR 90% FED. 10% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3475	3475
40600990	TEMPORARY RAMP	SQ YD	269	269
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	347	347
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	59	59
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	223	223
40603365	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	744	744
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	527	527
50102400	CONCRETE REMOVAL	CU YD	66.7	66.7
50157300	PROTECTIVE SHIELD	SQ YD	1400	1400
50300255	CONCRETE SUPERSTRUCTURE	CU YD	72.8	72.8
50300300	PROTECTIVE COAT	SQ YD	175	175
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12420	12420
50800515	BAR SPLICERS	EACH	136	136
52000110	PREFORMED JOINT STRIP SEAL	FOOT	406	406
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2247	2247
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2	2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	11	11
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2705	2705
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16510	16510
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5498	5498
70400100	TEMPORARY CONCRETE BARRIER	FOOT	925	925
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	925	925
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7356	7356
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	2786	2786
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	5234	5234
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	856	856

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN	0014 BRIDGE REPAIR 90% FED. 10% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
78200520	BARRIER WALL MARKERS, TYPE B	EACH	8	8
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2739	2739
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	100	100
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	20	20
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	300	300
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0062456	TEMPORARY PAVEMENT	SQ YD	12	12
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	2404	2404

FILE NAME = D264H71-shc-500.dgn
 PLOT DATE = 1/23/2012
 PLOT SCALE = 50.0000' / 1" IN.

CR & A CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED	-	G.F.L./K.R.K.	REVISED	-
DRAWN	-	K.R.K.	REVISED	-
CHECKED	-	E.J.M.	REVISED	-
DATE	-	JANUARY 2012	REVISED	-

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL ROUTE 5 AT I-74

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
205	181-2HB-13M	ROCK ISLAND	29	3
CONTRACT NO. 64H71				

SCALE: SHEET NO. OF SHEETS STA. TO STA.