

GENERAL NOTES

A minimum of 2 air monitors will be required to monitor abrasive blasting operations at each location, see special provision for "Containment and Disposal of Lead Paint Cleaning Residues".

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per LUMP SUM for CLEANING AND PAINTING STEEL BRIDGE NO. 1.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of CLEANING AND PAINTING STEEL BRIDGE NO. 1.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the CLEANING AND PAINTING STEEL BRIDGE NO. 1.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

INDEX OF SHEETS

1. Cover Sheet
2. General Notes, Index of Sheets, Standards
3. Summary of Quantities
5. -6. Traffic Control Plan
7. -17. Existing Plans Structure 081-0038
18. -20. Existing Plans 098-0081
21. -23. Existing Plans 098-0082

STANDARDS

- 701006-03
- 701101-02
- 701400-05
- 701402-09
- 701406-06
- 701426-04
- 701606-08
- 701801-05
- 701901-02
- 704001-07
- 720011-01
- 728001-01
- 729001-01

FILE NAME =	USER NAME = lankdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0:\BR\Bridge Painting\Contracts\PAINTING	2012-1\PLA\eng.dgn	DRAWN -	REVISED -		var	D2 Bridge Painting 2012-1	Various	24	2
	PLOT SCALE = 50.0038' / in.	CHECKED -	REVISED -		CONTRACT NO. 64HB6				
	PLOT DATE = Wed Jan 25 14:32:09 2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT				