

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE ROADWAY 0014 RURAL
44201027	CLASS B PATCHES, TYPE I, 15 INCH	SO YD	5	5
50102400	CONCRETE REMOVAL	CU YD	21.4	21.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21.4	21.4
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2870	2870
50800515	BAR SPLICERS	EACH	24	24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	205	205
67100100	MOBILIZATION	L SUM	1	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5122	5122
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1640	1640
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1425	1425
• 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	10420	10420
• 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	1364	1364
• 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1808	1808
• 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	258	258
78300100	PAVEMENT MARKING REMOVAL	SO FT	5852	5852
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	500	500
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	2	2
X5030530	FLOOR DRAINS EXTENSION	EACH	1	1
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	2
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	126	126
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH ^{EQUAL TO OR} LESS THAN 5 INCHES)	SO FT	19	19
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	12	12
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	110	110
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	76	76
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
* 78100100	^{REFLECTIVE} RAISED PAVEMENT MARKER	EACH	126	126

• SPECIALITY ITEMS

FILE NAME =	USER NAME = patelij	DESIGNED - RON WOODSHANK	REVISED -
c:\pwork\pwork\patelij\02273391\0366889-sht-details.dgn		DRAWN - RON WOODSHANK	REVISED -
PLOT SCALE = 1/8" = 1'		CHECKED -	REVISED -
PLOT DATE = 2/16/2012		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-2BR)	LASALLE	29	3
CONTRACT NO. 66889			ILLINOIS FED. AID PROJECT	

Rev.