

# SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	TOT. QTY	CONSTRUCTION TYPE CODE	
					IL 78 FULTON	NO. 0021
					NO. 0005	SIGNALS
					80% FED	80% FED
					20% STATE	10% STATE
		10% CITY				
	40600215	POLMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	13	13	
	40600300	AGGREGATE (PRIME COAT)	TON	78	78	
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	4525	4525	
	40600990	TEMPORARY RAMP	SQ YD	526	526	
	40603560	POLMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	3836	3836	
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	540	540	
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	75		75
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	34677	34677	
	44000600	SIDEWALK REMOVAL	SQ FT	75		75
	44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	196	196	
	44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	132	132	
	44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	52	52	
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6072	6072	
	67100100	MOBILIZATION	L SUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	

USER NAME = appenzeller-ji PLOT SCALE = 1:1144' / in. PLOT DATE = 2/1/2012	DESIGNED - _____ DRAWN - _____ CHECKED - _____ DATE - _____	REVISED - _____ REVISED - _____ REVISED - _____ REVISED - _____	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b> SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____	F.A.P. RTE. 22 SECTION 135RS-7 COUNTY FULTON TOTAL SHEETS 33 SHEET NO. 8 CONTRACT NO. 68978 ILLINOIS FED. AID PROJECT
--	--	--	---	---	---