

# SUMMARY OF QUANTITIES

|   |          |  |       |          | CONSTRUCTION TYPE CODE |           |
|---|----------|--|-------|----------|------------------------|-----------|
|   |          |  |       |          | IL 78 FULTON           | NO. 0021  |
|   |          |  |       |          | NO. 0005               | SIGNALS   |
|   |          |  |       |          | 80% FED                | 80% FED   |
|   |          |  |       |          | 20% STATE              | 10% STATE |
|   | CODE NO. | ITEM   | UNIT  | TOT. QTY |                        | 10% CITY  |
| X | 81028340 | UNDERGROUND CONDUIT,PVC,1 1/2" DIA.                | FOOT  | 40       |                        | 40        |
| X | 87301245 | ELECTRIC CABLE IN CONDUIT,SIGNAL NO.14 5C          | FOOT  | 1189     |                        | 1189      |
| X | 87301515 | ELECTRIC CABLE IN CONDUIT,LEAD-IN,NO. 18 3 PAIR    | FOOT  | 472      |                        | 472       |
| X | 87900200 | DRILL EXISTING HANDHOLE                            | EACH  | 4        |                        | 4         |
| X | 88030050 | SIGNAL HEAD,LED, 1-FACE, 3-SECTION,BRACKET MOUNTED | EACH  | 3        |                        | 3         |
| X | 88102740 | PEDESTRIAN SIGNAL HEAD,LED, 2-FACE,BRACKET MOUNTED | EACH  | 4        |                        | 4         |
| X | 88500100 | INDUCTIVE LOOP DETECTOR                            | EACH  | 9        |                        | 9         |
| X | 88600100 | DETECTOR LOOP,TYPE I                               | FOOT  | 1689     |                        | 1689      |
| X | 88800100 | PEDESTRIAN PUSH-BUTTON                             | EACH  | 8        |                        | 8         |
| X | 89502105 | REBUILD EXISTING SIGNAL HEAD,LED                   | EACH  | 8        |                        | 8         |
| X | 89502210 | MODIFY EXISTING CONTROLLER CABINET                 | EACH  | 1        |                        | 1         |
| X | 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT           | EACH  | 1        |                        | 1         |
|   | X2020110 | GRADING AND SHAPING SHOULDERS                      | UNIT  | 24       | 24                     |           |
| X | Z0033002 | LED SIGNAL FACE RETROFIT,RED BALL                  | EACH  | 5        |                        | 5         |
| X | Z0033004 | LED SIGNAL FACE RETROFIT,GREEN BALL                | EACH  | 5        |                        | 5         |
| X | Z0033008 | LED SIGNAL FACE RETROFIT,YELLOW BALL               | EACH  | 5        |                        | 5         |
|   | Z0034105 | MATERIAL TRANSFER DEVICE                           | TON   | 3836     | 3836                   |           |
|   | Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE            | L SUM | 1        | 1                      |           |

X SPECIALTY  
ITEM

|  |  |  |   |   |   |
|--|--|--|---|---|---|
| USER NAME = appenzeller,jj<br>PLOT SCALE = 1/8" = 1' / in.<br>PLOT DATE = 2/1/2012 | DESIGNED - _____<br>DRAWN - _____<br>CHECKED - _____<br>DATE - _____ | REVISED - _____<br>REVISED - _____<br>REVISED - _____<br>REVISED - _____ | <b>STATE OF ILLINOIS</b><br><b>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b><br>SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____ | F.A.P. RTE. 22<br>SECTION 135RS-7<br>COUNTY FULTON<br>TOTAL SHEETS 33<br>SHEET NO. 10<br>CONTRACT NO. 68978<br><small>ILLINOIS FED. AID PROJECT</small> |
|--|--|--|---|---|---|