

TABULATION OF RESURFACING QUANTITIES													
LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	BITUMINOUS SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	BITUMINOUS SURFACE REMOVAL 2"	BITUMINOUS MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	INCIDENTAL SURF CSE MIX C N50	POLY HMA SURF CSE MIX E N50	MATERIAL TRANSFER DEVICE		
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON
Locust Main Line (IL 78)													
STA. 24 + 56 TO 24 + 78	38.00	22.00	92.80	92.80	15.55		0.03	0.18		10.40	10.40		
STA. 24 + 78 TO 26 + 06	38.00	128.00	540.44			540.44	0.18	1.08		60.43	60.43		
STA. 26 + 48 TO 26 + 60	46.50	12.00	62.00			62.00	0.02	0.12	7.00				
STA. 26 + 60 TO 26 + 98	33.00	38.00	139.33	139.33	18.33		0.04	0.27	15.60				
Locust Main Line (IL 78)													
Right Turn Lane													
STA. 0 + 00 TO 0 + 22	11.00	22.00	26.80	26.80	6.11		0.01	0.05		3.00	3.00		
STA. 0 + 22 TO 0 + 96	15.75	74.00	129.00			129.00	0.04	0.25		14.44	14.44		
STA. 0 + 96 TO 1 + 76	22.00	80.00	195.00			195.00	0.06	0.39		21.84	21.84		
STA. 1 + 76 TO 2 + 25	19.50	49.00	106.00			106.00	0.03	0.21		11.87	11.87		
5th Ave Main Line (IL 78)													
STA. 25 + 52 TO 25 + 82	47.00	30.00	156.66	156.66	18.88		0.05	0.31	17.54				
STA. 25 + 82 TO 26 + 42	42.00	60.00	280.00			280.00	0.10	0.56		31.36	31.36		
STA. 26 + 42 TO 27 + 39	12.00	97.00	129.33			129.33	0.04	0.25		14.48	14.48		
STA. 26 + 42 TO 27 + 39	23.00	97.00	247.88			247.88	0.08	0.49		27.76	27.76		
STA. 27 + 39 TO 30 + 82	58.00	343.00	2210.44			2210.44	0.75	4.42		247.57	247.57		
STA. 30 + 82 TO 34 + 82	52.00	400.00	2311.11			2311.11	0.78	4.62		258.84	258.84		
STA. 34 + 82 TO 39 + 82	40.50	500.00	2250.00			2250.00	0.76	4.50		252.00	252.00		
STA. 39 + 82 TO 67 + 82	43.00	2800.00	13377.77			13377.77	4.54	26.75		1498.31	1498.31		
STA. 67 + 82 TO 69 + 82	16.00	200.00	355.55			355.55	0.12	0.71		39.82	39.82		
STA. 67 + 82 TO 69 + 82	26.00	200.00	577.77			577.77	0.20	1.15		64.71	64.71		
STA. 69 + 82 TO 70 + 21	7.00	39.00	30.33			30.33	0.01	0.06		3.40	3.40		
STA. 70 + 21 TO 74 + 21	43.50	400.00	1933.33			1933.33	0.65	3.86		216.53	216.53		
STA. 74 + 21 TO 87 + 21	31.00	1300.00	4477.77			4477.77	1.52	8.95		501.51	501.51		
STA. 87 + 21 TO 96 + 21	24.00	900.00	2400.00			2400.00	0.81	4.80		268.80	268.80		
STA. 96 + 21 TO 96 + 54	24.00	33.00	88.00	88.00	13.33		0.03	0.17		9.85	9.85		
Shoulder													
STA. 87 + 21 TO 96 + 21	8.00	900.00	800.00			800.00	0.27	1.60		89.60	89.60		
STA. 96 + 21 TO 96 + 54	8.00	33.00	29.33	29.33	4.44		0.01	0.05		3.28	3.28		
East Linn Street (IL9)													
	38.00	252.00	1064.00			1064.00	0.36	2.12		119.16	119.16		
			10.55			10.55	0.00	0.02		1.21	1.21		
East Linn Street (IL9)													
	38.00	30.00	126.66	126.66	21.11		0.04	0.25		14.18	14.18		
East Linn Street (IL9) RT TURN LN													
STA. 0 + 00 TO 0 + 96			6.00			6.00	0.00	0.01		0.67	0.67		
STA. 0 + 96 TO 1 + 59	12.50	63.00	87.50			87.50	0.03	0.17		9.80	9.80		
STA. 1 + 59 TO 2 + 05	19.00	46.00	97.11			97.11	0.03	0.19		10.87	10.87		
STA. 2 + 05 TO 2 + 57	40.00	52.00	231.11			231.11	0.07	0.46		25.88	25.88		
East Linn St. Median Rt. Turn Ln.													
STA. 0 + 00 TO 0 + 24			2.27			2.27	0.00	0.00		0.25	0.25		
STA. 0 + 24 TO 0 + 41	3.00	17.00	5.66			5.66	0.00	0.01		0.63	0.63		
STA. 0 + 41 TO 0 + 67	5.00	26.00	14.44			14.44	0.00	0.02		1.61	1.61		
STA. 0 + 67 TO 0 + 81	14.00	14.00	21.77			21.77	0.01	0.04		2.43	2.43		
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
STA. 0 + 00 TO 0 + 00													
GRAND-TOTAL				780	98	33,954	11.7	69.1	40	3,836	3,836		

USER NAME = appenzellerJJ	DESIGNED -	REVISED -
PLOT SCALE = 1/8" = 1' in.	DRAWN -	REVISED -
PLOT DATE = 1/25/2012	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES		
SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____

F.A.P. RTE. 22	SECTION 135E(ZRS-2, X)RS-1J	COUNTY FULTON	TOTAL SHEETS 33	SHEET NO. 17
ILLINOIS FED. AID PROJECT				
CONTRACT NO. 68978				