TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	BITUMINOUS SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	BITUMINOUS SURFACE REMOVAL	BITUMINOUS MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	INCIDENTAL SURF CSE MIX C N50	POLY HMA SURF CSE MIX E N50	MATERIAL TRANSFER DEVICE
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON
East Chestnut	102.00	18.00	204.00			204.00	0.07	0.40	22.84		
East Chestnut	47.00	30.00	156.66	156.66	26.11		0.05	0.31	17.54		
West Chestnut	74.00	48.00	394.66			394.66	0.13	0.79	44.20		
West Chestnut	33.00	30.00	110.00	110.00	18.33		0.03	0.22	12.32		
East Elm	58.50	17.00	110.50	110.50	18.88		0.03	0.22	12.37		
West Elm	70.50	39.00	305.50	305.50	22.22		0.10	0.61	34.21		
East Pine	20.50	26.00	59.22	59.22	8.33		0.02	0.11	6.63		
West Pine	48.00	28.00	149.33	149.33	12.77		0.05	0.29	16.72		
East Walnut	45.50	18.00	91.00	91.00	13.33		0.03	0.18	10.20		
West Walnut	46.50	29.00	149.83	149.83	13.33		0.05	0.30	16.78		
East Maple	47.00	37.00	193.22	193.22	13.33		0.06	0.38	21.64		
West Maple	46.00	31.00	158.44	158.44	12.22		0.05	0.31	17.74		
East Anderson	48.50	23.00	124.00			124.00	0.04	0.24	13.88		
East Anderson	26.00	30.00	86.66	86.66	14.44		0.03	0.17	9.70		
East Grant	45.00	26.00	130.00	130.00	15.00		0.04	0.26	14.56		
East Oak	44.50	33.00	163.16	163.16	14.44		0.05	0.32	18.27		
West Oak	47.50	27.00	142.50	142.50	15.00		0.04	0.28	16.00		
East Hickory	49.50	30.00	165.00	165.00	13.88		0.05	0.33	18.48		
West Hickory	48.50	30.00	161.66	161.66	13.33		0.05	0.32	18.10		
East Cherry	43.50	32.00	154.66	154.66	12.22		0.05	0.31	17.32		
West Cherry	45.50	30.00	151.66	151.66	12.77		0.05	0.30	17.00		
East Holly	48.50	19.00	102.38	102.38	18.88		0.03	0.20	11.46		
West Holly	50.00	21.00	116.66	116.66	19.44		0.04	0.23	13.06		
East Lewis	52.00	24.00	138.66	138.66	18.88		0.04	0.27	15.53		
West Lewis	50.00	27.00	150.00	150.00	19.44		0.05	0.30	16.80		
East Hanlon	54.50	24.00	145.33	145.33	19.44		0.05	0.29	16.27		
West Hanlon	52.50	24.00	140.00	140.00	19.44		0.04	0.28	15.68		
East Sam Scott	67.00	25.00	186.11	186.11	27.22		0.06	0.37	20.84		
West Sam Scott	47.50	24.00	126.66	126.66	15.55		0.04	0.25	14.18		
5TH AVE (IL78/IL9) TOTALS				780.00	98.00	33954.00	11.70	69.10	40.00	3836.00	3836.00
GRAND-TOTAL				**4,525**	**526**	**34,677**	**13.1**	**77.9**	**540**	**3,836**	**3,836**