

**COMMITMENTS**

No Commitments have been made for this project

**GENERAL NOTES**

All cleaning and painting shall be as specified in the Special Provision for "Clening and Painting Existing Structural Steel" All beams, Brackets and all other structural steel shall be cleaned per Near White Blast Cleaning SSPC-SP10 according to the following schedule:

Bridge Location 1 and 2 . Entier structure.  
Recycled steel abrasive shall be used for both structures.

The final finish coat for the fascia beams shall be according to the following schedule:  
Bridge Location 1 and 2 shall be Red Brown ( Munsel No. 2.5YR 3/4)

The final finish coat for the underside shall be according to the the following schedule:  
Bridge Location 1 and 2 shall be Light Grey(Munsel No. 5B 7/1)

No Air Monitors for this Project.

FILE NAME = April 2012 painting.dgn	USER NAME = AdodeSA	DESIGNED - _____	REVISED - _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____		F.A.I. RTE. 39	SECTION 102-[4HB]3HB-2J	COUNTY WOODFORD	TOTAL SHEETS 12	SHEET NO. 3
		DRAWN - _____	REVISED - _____					CONTRACT NO. 68A94		ILLINOIS FED. AID PROJECT	
		PLOT SCALE = 2.0205' / 1in.	CHECKED - _____								
		PLOT DATE = 2/1/2012	DATE - _____								