

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAS 533 (MARKET ST)
 RURAL
 COUNTY: CHAMPAIGN
 STA 106+50.00
 TO
 STA 162+24.00
 FUNDING BREAKOUT: 80% FEDERAL
 20% STATE
 CONSTRUCTION TYPE CODE: 0005

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,520.0
40600300	AGGREGATE (PRIME COAT)	TON	30.0
40600990	TEMPORARY RAMP	SQ YD	140.0
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,629.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	174.0
40800030	AGGREGATE (PRIME COAT)	TON	4.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	195.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	14,960.0
44022039	PARTIAL DEPTH REMOVAL 5 1/2"	SQ YD	485.0
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	157.0
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	17.0
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	58.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	205.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	73.0

FILE NAME =	USER NAME = piersonbr	DESIGNED - SEL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\piersonbr\d0249274\0570874-shr-500.dgn	DRAWN - BBP	REVISED -	533					(10-34,HB-5,106)RS-1	CHAMPAIGN	26	4	
PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -	SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.					CONTRACT NO. 70874				
PLOT DATE = 1/27/2012	DATE - 02/24/11	REVISED -	ILLINOIS FED. AID PROJECT									