

SCHEDULE OF QUANTITIES

SHEET 3 OF 4

INCIDENTAL HOT-MIX ASPHALT SCHEDULE

STATION	LOCATION	AREA (SQ YD)	INCIDENTAL HMA THICKNESS (INCHES)	X4400196	40800050	40800010	40800030
				HMA SURFACE REMOVAL, SPECIAL (SQ YD)	INCIDENTAL HMA SURFACING (TON)	BIT MATLS PRIME COAT (GALLON)	AGGREGATE PRIME COAT (TON)
107+32.88	LT MAINLINE	65.00	2.00	65.00	7.28	6.50	0.13
111+01.01	LT MAINLINE	40.00	2.00	40.00	4.48	4.00	0.08
112+73.13	LT MAINLINE	58.00	2.00	58.00	6.50	5.80	0.12
111+71.30	RT MAINLINE	62.00	2.00	62.00	6.94	6.20	0.12
111+88.89	LT MAINLINE	45.00	2.00	45.00	5.04	4.50	0.09
114+00.04	LT MAINLINE	16.00	2.00	16.00	1.79	1.60	0.03
118+58.54	RT MAINLINE	12.00	2.00	12.00	1.34	1.20	0.02
127+90.00	RT LEVERETT ROAD	1440.00	2.00	1440.00	161.28	144.00	2.88
TOTAL =				1738.00	194.66	173.80	3.48
USE =				1738.00	195.00	174.00	4.00
				SQ YD	TON	GALLON	TON

70300100 SHORT TERM PAVEMENT MARKING

LOCATION	STATION	TO	STATION	LENGTH (FT)	QUANTITY (FT)	APPLY AFTER	COLOR
CL.	106+50.00		114+87.77 (BK)	87.78	175.55	MILLING & HMA SURFACE	YELLOW
CL.	109+05.49 (AH)		136+85.00	281.95	563.90	MILLING & HMA SURFACE	YELLOW
CL.	149+62.00		162+24.00	130.20	260.40	MILLING & HMA SURFACE	YELLOW
TOTAL =					999.86	FT	
USE =					1000.00	FT	

78301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	STATION	TO	STATION	LENGTH (FT)	AREA (SQ FT)	
C.L.	106+50.00		114+87.77 (BK)	87.78	28.97	
C.L.	109+05.49 (AH)		136+85.00	281.95	93.04	
C.L.	149+62.00		162+24.00	130.20	42.97	
TOTAL =					164.98	SQ FT
USE =					165.00	SQ FT

48102100 AGGREGATE WEDGE SHOULDERS TYPE B

LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AREA (TON)
N.B. MAINLINE	106+50.00		113+86.00	736.00	3.00	15.31
N.B. MAINLINE	113+86.00		114+87.77 (BK)	101.77	3.50	2.47
N.B. MAINLINE	109+05.49 (AH)		120+50.00	1144.51	3.00	23.81
N.B. MAINLINE	128+75.00		136+85.00	810.00	3.00	16.85
N.B. MAINLINE	149+62.00		162+24.00	1262.00	3.00	31.25
N.B. LEVERETT RD	10+13.00		11+69.00	312.00	2.00	4.33
S.B. MAINLINE	106+50.00		114+87.77 (BK)	837.77	3.00	17.43
S.B. MAINLINE	109+05.49 (AH)		136+85.00	2779.51	3.00	57.81
S.B. MAINLINE	149+62.00		162+24.00	1262.00	3.50	35.62
TOTAL =						204.87 TON
USE =						205.00 TON

78001110 PAINT PAVEMENT MARKING - LINE 4'

LOCATION	STATION	TO	STATION	LENGTH (FT)
C.L.	SKIP - DASH YELLOW	106+50.00	114+87.77 (BK)	210.00
C.L.	SKIP - DASH YELLOW	109+05.49 (AH)	162+24.00	1330.00
C.L.	SOLID YELLOW	136+85.00	149+62.00	1277.00
N.B.	SOLID WHITE	106+50.00	114+87.77 (BK)	837.77
N.B.	SOLID WHITE	109+05.49 (AH)	162+24.00	5318.51
LEVERETT RD	SOLID YELLOW	10+44.00	11+69.00	250.00
S.B.	SOLID WHITE	106+50.00	114+87.77 (BK)	837.77
S.B.	SOLID WHITE	109+05.49 (AH)	162+24.00	5318.51
TOTAL =				15,379.56 FT
USE =				15,380.00 FT