SUMMARY OF QUANTITIES

LOCATION OF WORK: FAU 7045 BOWMAN AVE. & I-74 EB RAMPS 100% STATE

CONSTRUCTION TYPE CODE: URBAN 0021

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	3.5	3.5
35300720	PORTLAND CEMENT CONCRETE BASE COURSE 13"	SQ YD	28.0	28.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	81.0	81.0
60500050	REMOVING CATCH BASINS	EACH	1.0	1.0
67100100	MOBILIZATION	L SUM	1.0	1.0
~~70100700~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701406~~	~~L SUM~~	~~1.0~~	~~1.0~~
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	98.0	98.0
80500100	SERVICE INSTALLATION, TYPE A	EACH	1.0	1.0
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	104.0	104.0
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	565.0	565.0
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	691.0	691.0
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	152.0	152.0
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	256.0	256.0
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	38.0	38.0
81028400	UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	4.0	4.0
81400100	HANDHOLE	EACH	9.0	9.0
81400300	DOUBLE HANDHOLE	EACH	1.0	1.0
81500100	GULFBOX JUNCTION	EACH	2.0	2.0
83057170	LIGHT POLE, WOOD, 35 FOOT, CLASS 3	EACH	1.0	1.0
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1.0	1.0
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1.0	1.0
87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125 6F	FOOT	861.0	861.0
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,628.0	1,628.0
87301115	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 2C	FOOT	861.0	861.0
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	532.0	532.0
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO 14 1C	FOOT	809.0	809.0
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	1,875.0	1,875.0
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	34.0	34.0
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,421.0	1,421.0

*SPECIALTY ITEM