

SUMMARY OF QUANTITIES (cont.)

LOCATION OF WORK:

FAU 7045
BOWMAN AVE.
&
I-74 EB RAMPS
100% STATE

URBAN

0021

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	5.0	5.0
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1.0	1.0
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1.0	1.0
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1.0	1.0
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1.0	1.0
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18.6	18.6
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3.5	3.5
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10.0	10.0
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	24.0	24.0
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6.0	6.0
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6.0	6.0
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1.0	1.0
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1.0	1.0
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	6.0	6.0
88500100	INDUCTIVE LOOP DETECTOR	EACH	11.0	11.0
88600100	DETECTOR LOOP, TYPE I	FOOT	601.0	601.0
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	82.0	82.0
X6061354	CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)	SQ FT	20.0	20.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	9.0	9.0
XX007251	INTERSECTION VIDEO TRAFFIC MONITORING SYSTEM WITH PTZ CAMERA	EACH	1.0	1.0

FILE NAME *	USER NAME * biggard	DESIGNED - RDB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\biggard\0277273\0570	958-Design.dgn	DRAWN - RDB	REVISED -		7045	(92-12)TS	VERMILION	11	4
PLOT SCALE * 40.0000 ' / in.	CHECKED -	REVISED -			SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____				
PLOT DATE * 2/3/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 70958				