

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				ROADWAY 80% FEDERAL 20% STATE 0005
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	103	103
44213100	PAVEMENT FABRIC	SQ YD	223	223
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,135	3,135
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	4,107	4,107
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	1	1
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1	1
54215547	METAL END SECTIONS 12"	EACH	2	2
54390180	INSERTION CULVERT LINER 24"	FOOT	45	45
54390210	INSERTION CULVERT LINER 30"	FOOT	139	139
54390230	INSERTION CULVERT LINER 36"	FOOT	47	47
60100945	PIPE DRAINS 12"	FOOT	16	16
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	10.5	10.5
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	2	2
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	550	550

SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				ROADWAY 80% FEDERAL 20% STATE 0005
* 63000007	STEEL PLATE BEAM GUARDRAIL, TYPE B, 6 FOOT POSTS	FOOT	150	150
* 63000370	LONG-SPAN GUARDRAIL OVER CULVERT, 25 FT SPAN	FOOT	50	50
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5,612	5,612
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	55,364	55,364
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	617	617
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1,052	1,052

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -
c:\pwwork\pwwidat\sparksgw\d0216263\0672243-sht-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

SPECIALTY ITEM

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
						304	4RS-3, BR-1	PIKE	41	4
ILLINOIS FED. AID PROJECT										CONTRACT NO. 72243