

CODE NO	SUMMARY OF QUANTITIES  ITEM	UNIT	TOTAL QUANTITY	NHF (L25E)		F (L25E)	
				FAP 317 (US 24)		FAS 587 (US 24 SPUR)	
				80% FEDERAL 20% STATE		80% FEDERAL 20% STATE	
				CONSTRUCTION TYPE CODE			
				0005		0005	
20200600	EXCAVATING AND GRADING EXISTING SHOULDERS	UNIT	319	319		0	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	39	39		0	
35800100	PREPARATION OF BASE	SQ YD	225	136		89	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	21	12		9	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22.8	21.6		1.2	
40600300	AGGREGATE (PRIME COAT)	TON	118	113		5	
40600635	LEVELING BINDER (MACHINE METHOD) N70	TON	1,829	1,670		159	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		0	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,449	2,173		276	
40600990	TEMPORARY RAMP	SQ YD	570	547		23	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	4,837	4,597		240	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	364	295		69	
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,162	5,162		0	
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	50	0		50	
44200202	PAVEMENT PATCHING, TYPE II, 17 INCH	SQ YD	150	150		0	
44200204	PAVEMENT PATCHING, TYPE III, 17 INCH	SQ YD	80	80		0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,556	2,414		142	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	14,575	14,401		174	
* 63000001	STEEL PLATE BEAM GUARDRAIL, (TYPE A), 6 FOOT POSTS	FOOT	400	400		0	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		0	
63200310	GUARDRAIL REMOVAL	FOOT	600	600		0	
64200108	SHOULDER RUMBLE STRIP, 8 INCH	FOOT	30,533	30,533		0	

\*SPECIALTY  
ITEM

FILE NAME =	USER NAME = sparksgu	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES FAP 317 (US 24)				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pvc\work\pwidot\sparksgu\0215228\0672884.sht-S00.dgn	2884.sht-S00.dgn	DRAWN -	REVISED -					SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	317	GRS-7	BROWN
PLOT SCALE = 100.0000 ' / in.		CHECKED -	REVISED -									CONTRACT NO. 72884				
PLOT DATE = Feb-06-2012 02:58:15PM		DATE -	REVISED -									ILLINOIS FED. AID PROJECT				