

PAVEMENT SCHEDULE								
LOCATION			HMA SURFACE	LEVELING	HMA SURFACE	BITUMINOUS	AGGREGATE	
STATION TO STATION	LENGTH (FT)	WIDTH (FT)	REMOVAL - BUTT JOINT (SQ YD)	BINDER (MM) (TON)	CSE MIX "C", N70 (1 1/2") (TON)	MATERIAL PRIME COAT (TON)	PRIME COAT (TON)	
FAP 317 (US 24)								
STA. 214+26.03 TO STA. 214+88.03	62.00	VARIES	97.2	6.4	15.9	0.07	0.38	
STA. 214+88.03 TO STA. 232+48.00	1,759.97	22 L.B./30 SURF	0	180.7	492.8	2.23	11.73	
STA. 232+48.00 TO STA. 235+48.00	300.00	22 L.B./30 SURF	0	30.8	106.4	0.48	2.53	
STA. 235+48.00 TO STA. 244+66.00	918.00	22 L.B./30 SURF	0	94.2	257.0	1.16	6.12	
STA. 244+66.00 TO STA. 247+66.00	300.00	22 L.B./30 SURF	0	30.8	106.4	0.48	2.5	
STA. 244+66.00 TO STA. 373+31.10	12,865.10	22 L.B./30 SURF	0	1,320.8	3602.2	16.30	85.77	
STA. 373+31.10 TO STA. 373+93.10	62.00	VARIES	97.2	6.4	15.9	0.07	0.38	
		SUB TOTAL	194	1670	4597	20.8	109	
FAS 587 (US 24 SPUR)								
STA. 723+66.78 TO STA. 731+80.66	813.88	VARIES	0	18.1	36.2	0.16	0.2	
STA. 731+80.66 TO STA. 733+78.80	198.14	18	0	16.6	34.1	0.2	0.8	
STA. 733+78.80 TO STA. 738+71.92	493.12	18	0	41.4	85.0	0.4	2.0	
STA. 738+71.92 TO STA. 741+50.39	278.47	18	0	23.4	48.0	0.2	1.1	
STA. 741+50.39 TO STA. 742+41.27	90.88	VARIES	0	18.1	36.2	0.16	0.2	
		SUB TOTAL	0	159	240	1.1	4	
		GRAND TOTAL	*194	1,829	4,836	*22	*114	

*ADDITIONAL QUANTITIES OF THESE PAY ITEMS ARE INCLUDED IN THE ENTRANCE SCHEDULE.

TREE REMOVAL		
LOCATION		QUANTITY (UNIT)
FAP 317 (US 24)		
STA. 374+83	- 30' LT	39
	TOTAL	39

TELESCOPING STEEL SIGN SUPPORT	
LOCATION STATION	QUANTITY (FOOT)
FAS 587 (US 24 SPUR)	
RIGHT	
STA. 729+34.00	8
STA. 729+54.00	8
LEFT	
STA. 729+50.00	8
STA. 729+70.00	8
	TOTAL
	32

TERMINAL MARKERS, DIRECT APPLIED	
LOCATION STATION	QUANTITY (EACH)
FAP 317 (US 24)	
RIGHT	
STA. 232+48.00	1
STA. 235+48.00	1
STA. 244+66.00	1
STA. 247+66.00	1
	TOTAL
	4

STEEL PLATE BEAM GUARDRAIL, (TYPE A), 6 FOOT POSTS			
LOCATION			LENGTH (FT)
STATION TO STATION			
FAP 317 (US 24)			
RIGHT			
STA. 232+98.00	TO	STA. 234+98.00	200.00
STA. 245+16.00	TO	STA. 247+16.00	200.00
		TOTAL	400.00

GUARDRAIL REMOVAL	
LOCATION	LENGTH (FT)
STATION TO STATION	
FAP 317 (US 24)	
RIGHT	
STA. 232+48.00 TO STA. 235+48.00	300.0
STA. 244+66.00 TO STA. 247+66.00	300.0
	TOTAL
	600.0

TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT			
LOCATION			QUANTITY (EACH)
STATION TO STATION			
FAP 317 (US 24)			
RIGHT			
STA. 232+48.00	TO	STA. 232+98.00	1.00
STA. 234+98.00	TO	STA. 235+48.00	1.00
STA. 244+66.00	TO	STA. 245+16.00	1.00
STA. 247+16.00	TO	STA. 247+66.00	1.00
		TOTAL	4.00

GUARDRAIL MARKERS, TYPE A	
LOCATION	QUANTITY (EACH)
STATION TO STATION	
FAP 317 (US 24)	
RIGHT	
STA. 232+48.00 TO STA. 235+48.00	4
STA. 244+66.00 TO STA. 247+66.00	4
	TOTAL
	8

OBJECT MARKER - TYPE 3	
LOCATION STATION	QUANTITY (EACH)
FAS 587 (US 24 SPUR)	
RIGHT	
STA. 729+34.00	1
STA. 729+54.00	1
LEFT	
STA. 729+50.00	1
STA. 729+70.00	1
	TOTAL
	4