

FAU CH 17
CONSTRUCTION TYPE CODE

FAU CH 17
CONSTRUCTION TYPE CODE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN	RURAL
				L25EU	L25EG
Z00A9799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	2	1	1
20200100	EARTH EXCAVATION	CU YD	75		75
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	135	49	86
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80		80
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SO YD	620		620
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	321	135	186
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1813	753	1060
40600300	AGGREGATE (PRIME COAT)	TON	36	15	21
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	136		136
40600990	TEMPORARY RAMP	SO YD	81	70	11
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1694	310	1384
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1561	659	902
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	327	132	195
44000100	PAVEMENT REMOVAL	SO YD	450		450

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN	RURAL
				L25EU	L25EG
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	871	871	
44000400	GUTTER REMOVAL	FOOT	1074		1074
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	9	9	
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	203	203	
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	16	16	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1214	455	759
67100100	MOBILIZATION	L SUM	1	0.4	0.6
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.4	0.6
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.4	0.6
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.4	0.6
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4		4
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2162	800	1362
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	243	90	153
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	102	102	

*SPECIALTY ITEM

FILE NAME =	USER NAME = swartzv	DESIGNED -	REVISED -
ei:\p\work\p\pidot\swartzv\d0283756\077	*465-shl-saq.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 "/ in.	CHECKED -	REVISED -
	PLOT DATE = 2/10/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE: NA	SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7623	(39MFT)RS-1	COLES	31	3
CONTRACT NO. 74465			ILLINOIS FED. AID PROJECT	