

STATION TO STATION	LENGTH	AVERAGE WIDTH OF RESURFACING (PAVEMENT PLUS HMA SHOULDERS)	AREA	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	EXCAVATING AND GRADING EXISTING SHOULDER	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
FOOT	FOOT	SO YD	SO YD	SO YD	GALLON	TON	UNIT	TON	TON	TON	SO YD	
C. H. 17												
14+72.00 TO 16+26.00	154.00	VAR.	617	0	617	62	1.2	0.0	52	0	0	70
16+26.00 TO 16+86.00	60.00	20.0	133	0	133	13	0.3	1.2	11	0	10	0
16+86.00 TO 30+43.00	1357.00	20.0	3016	0	0	302	6.0	24.3	257	0	223	0
30+43.00 TO 31+03.00	60.00	20.0	133	0	0	13	0.3	1.2	11	9	10	0
31+03.00 TO 45+25.00	1422.00	20.0	3160	0	0	316	6.3	25.1	269	415	234	0
45+25.00 TO 76+95.00	3170.00	20.0	7044	0	0	704	14.1	56.8	599	924	521	0
76+95.00 TO 86+91.00	996.00	21.5	2379	0	0	238	4.8	19.9	202	311	164	0
86+91.00 TO 87+07.00	16.00	21.5	38	38	0	4	0.1	0.3	3	5	3	0
87+07.00 TO 87+51.00	44.00	20.0	98	98	0	10	0.2	0.9	8	6	7	11
4' TAPERS ON ENTRANCES												
ENTRANCE TOTALS												
4.00	VAR.	0	0	18	0.4	0.0	15	23	0	0		
FRONTAGE ROAD												
1100+10.00 TO 1100+40.00	30.00	VAR.	121	0	121	12	0.2	0.6	10	0	5	0
1100+40.00 TO 1102+37.00	197.00	20.0	438	0	0	35	0.7	3.9	52	0	32	0
1102+37.00 TO 1102+67.00	30.00	20.0	67	0	0	86	1.7	0.6	72	0	5	0
TOTALS												
			17178	136	871	1813	36	135	1561	1694	1214	81

PAVEMENT MARKING SCHEDULE	LENGTH	PAINT PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
C. H. 17							
14+72.00 TO 16+86.00	214.0	54	102	46	22	43	7
16+86.00 TO 30+43.00	1357.0	339	0	0	0	407	45
30+43.00 TO 45+25.00	1482.0	371	0	0	0	445	49
45+25.00 TO 87+51.00	4226.0	1057	0	0	0	1268	141
TOTALS							
	7279	1820	102	46	22	2162	243

SURVEY MONUMENT SCHEDULE			PROTECTING OR RESETTING SURVEY MARKERS	SURVEY MARKER VAULT
STATION	O/S	DESCRIPTION		
			EACH	EACH
41+23.32	0	R. R. SPIKE IN PAVEMENT	1	1
72+90	0	MAG NAIL IN PAVEMENT	1	1
TOTALS			2	2

LOCATION	LENGTH FEET	DESCRIPTION
C. H. 17		
RT. STATION 76+95.00 TO 87+07.00	1012	V-GUTTER
RT. STATION 77+23.00	14	GUTTER OUTLET
RT. STATION 81+20.00	26	GUTTER OUTLET
RT. STATION 87+13.00	22	GUTTER OUTLET
TOTAL = 1074 FOOT		
REMOVAL OF GUTTER OUTLETS TO BE PAID FOR BY THE FOOT AS GUTTER REMOVAL		