

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0005		
Z0049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	5	5		
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	103	103		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	72	72		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2029	2029		
40600300	AGGREGATE (PRIME COAT)	TON	41	41		
40600990	TEMPORARY RAMP	SO YD	37	37		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1819	1819		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	8	8		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	7329	7329		
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	16	16		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	889	889		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	129	129		
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	27	27		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	381	381		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0005		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	2		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1847	1847		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11633	11633		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	242	242		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	52	52		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30	30		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	11633	11633		
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	102	102		
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	46	46		

*SPECIALTY ITEM

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
e:\pwork\pwork\stevfennk\d0282277\074553-sh1-soq.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 1/ in.	CHECKED -	REVISED -
	PLOT DATE = 1/25/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA	SHEET 1 OF 2 SHEETS	STA.	TO STA.	F.A.P. RTE. 779	SECTION 101 RS-2	COUNTY CRAWFORD	TOTAL SHEETS 17	SHEET NO. 3
							CONTRACT NO. 74553	
ILLINOIS FED. AID PROJECT								