

PAVING SCHEDULE

LOCATION			LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP	EXCAVATING AND GRADING EXISTING SHOULDERS
STATION	TO	STATION	FOOT	FOOT	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	SQ YD	UNIT
0+14.00	TO	2+30.84	216.8	VARIES	828.4		828.4	83	1.7	69.6		22.2	4.3
2+30.84	TO	2+60.84	30.0	24	80.0		80.0	8	0.2	7.4	2.3		0.6
2+60.84	TO	51+20.00	4859.2	24	12957.8	12958		1296	25.9	1201.9	376.3		97.2
51+20.00	TO	51+50.00	30.0	25	83.3		83.3	8	0.2	7.7	2.3		0.6
51+50.00	TO	61+71.12	1021.1	26	2949.9		2949.9	295	5.9	247.8			
61+71.12 BK	=	61+77.47 AH											
61+77.47	TO	72+24.11	1046.6	26	3023.6		3023.6	302	6.0	254.0			
72+24.11 BK	=	72+24.18 AH											
72+24.18		73+49.98	125.8	26	363.4		363.4	36	0.7	30.5		14.4	
TOTALS			7330		20286	12958	7329	2029	41	1819	381	37	103

PAVEMENT MARKING SCHEDULE

LOCATION			LENGTH	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS	PAINT PAVEMENT MARKING-LINE 8"	PAINT PAVEMENT MARKING-LINE 12"	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	PAINT PAVEMENT MARKING-LINE 4"
STATION	TO	STATION	FOOT	FOOT	SQ FT	EACH	FOOT	FOOT	FOOT	FOOT	FOOT
0+14.00	TO	2+30.84	216.8	65.1	7.2	3	102	46.0	30		54
2+30.84	TO	2+60.84	30.0	9.0	1.0	1					67
2+60.84	TO	51+20.00	4859.2	1,457.7	160.4	61					10,895
51+20.00	TO	51+50.00	30.0	9.0	1.0	1					68
51+50.00	TO	61+71.12	1021.1	306.3	33.7	13				52	255
61+71.12 BK	=	61+77.47 AH									0
61+77.47	TO	72+24.11	1046.6	314.0	34.5	13					262
72+24.11 BK	=	72+24.18 AH									0
72+24.18		73+49.98	125.8	37.7	4.2	2					31
SHEET TOTALS			7,330	1,847	242	90	102	46	30	52	11,633

PATCHING SCHEDULE

CLASS D PATCHES, TYPE I, 13" SQ. YD.	CLASS D PATCHES, TYPE II, 13" SQ. YD.	CLASS D PATCHES, TYPE III, 13" SQ. YD.	CLASS D PATCHES, TYPE IV, 13" SQ. YD.	PARTIAL DEPTH REMOVAL (VAR. DEPTH) SQ. YD.	HOT-MIX ASPHALT FOR PATCHING TON
16	889	129	27	276	93

SURVEY MARKERS SCHEDULE

LOCATION	OFFSET	SURVEY MARKER VAULT	PROTECTING OR RESETTING SURVEY MARKERS	PERMANENT SURVEY MARKERS
		EACH	EACH	EACH
23+56.87	0.3' LT.	1		1
49+91.38	1.34' LT	1	1	
58+52.53	0.0	1	1	
61+71.72 BK =	4.0' RT	1	1	
61+77.47 AH				
66+24.21	3.8' RT.	1	1	
72+24.19	3.8' RT.	1	1	
TOTAL		6	5	1