

PAVEMENT MARKING SCHEDULE		LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW)	TEMPORARY PAVEMENT MARKING-LINE 4" (WHITE)	WORK ZONE PAVEMENT MARKING REMOVAL	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	MODIFIED URETHANE PAVEMENT MARKING-LINE 4" (YELLOW)	MODIFIED URETHANE PAVEMENT MARKING-LINE 4" (WHITE)	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	AERIAL SPEED CHECK MARKING	GROOVING FOR RECESSED PAVEMENT MARKING-5"	GROOVING FOR RECESSED PAVEMENT MARKING-19"
STATION	TO STATION	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	FOOT
840+69.50	TO 841+44.50	75.0	93.0	150.0	150.0	109.0	37.5	150.0	150.0	4	4		300.0	
841+44.50	TO 841+64.63	20.1	24.9	40.3	40.3	29.3	10.1	40.3	40.3	1	1		80.5	
841+64.63	= 813+20.49	STA. EQ.												
813+20.49	TO 846+44.94	3,324.5	4,122.3	6,648.9	6,648.9	4,832.5	1,662.2	6,648.9	6,648.9	166	166		13,297.8	
846+44.94	TO 847+15.00	70.1	86.8	140.1	140.1	101.8	35.0	140.1	140.1	4	4		280.2	
847+15.00	TO 848+85.00	170.0	210.8	340.0	340.0	247.1	85.0	340.0	340.0	9	9		680.0	
848+85.00	TO 849+54.95	69.9	86.8	139.9	139.9	101.7	35.0	139.9	139.9	3	3		279.8	
849+54.95	TO 854+84.14	529.2	656.3	1,058.4	1,058.4	769.3	264.6	1,058.4	1,058.4	26	26		2,116.8	
854+84.14	TO 856+64.14	180.0	223.2	360.0	360.0	261.7	90.0	360.0	360.0	9	9		720.0	
856+64.47	TO 857+81.80	117.3	BRIDGE OMISSION											
857+81.80	TO 859+61.80	180.0	223.2	360.0	360.0	261.7	90.0	360.0	360.0	9	9		720.0	
859+61.80	TO 870+95.20	1,133.4	1,405.2	2,266.8	2,266.8	1,647.5	566.7	2,266.8	2,266.8	57	57		4,533.6	
870+95.20	TO 871+25.20	30.0	37.2	60.0	60.0	43.6	15.0	60.0	60.0	2	2		120.0	
871+25.20	TO 878+12.10	686.9	425.9	686.9	686.9	499.2	171.7	686.9	686.9	17	17		1,373.8	
878+12.10	TO 878+42.10	30.0	18.6	30.0	30.0	21.8	7.5	30.0	30.0	1	1		60.0	
878+41.20	TO 900+52.80	2,211.6	PAVING OMISSION											
900+52.80	TO 923+41.35	2,288.6	PAVING OMISSION											
923+41.35	TO 923+71.35	30.0	18.6	30.0	30.0	21.8	7.5	30.0	30.0	1	1		60.0	
923+71.13	TO 927+35.50	364.4	225.9	364.4	364.4	264.8	91.1	364.4	364.4	9	9		728.7	
927+35.50	TO 927+65.50	30.0	37.2	60.0	60.0	43.6	15.0	60.0	60.0	2	2		120.0	
927+65.50	TO 1055+43.99	12,778.5	15,845.5	25,557.0	25,557.0	18,575.1	6,389.2	25,557.0	25,557.0	639	639	72.0	51,114.0	72.0
1055+43.99	TO 1056+13.99	70.0	86.8	140.0	140.0	101.8	35.0	140.0	140.0	4	4		280.0	
1056+13.99	TO 1057+86.00	172.0	213.2	344.0	344.0	250.0	86.0	344.0	344.0	9	9		688.0	
1057+86.00	TO 1058+56.00	70.0	86.8	140.0	140.0	101.8	35.0	140.0	140.0	4	4		280.0	
1058+56.00	TO 1115+85.09	5,729.1	7,104.3	11,458.2	11,458.2	8,328.0	2,864.5	11,458.2	11,458.2	286	286		22,916.4	
1115+85.09	TO 1116+55.00	69.9	86.7	139.8	139.8	101.6	35.0	139.8	139.8	3	3		279.6	
1116+55.00	TO 1116+70.00	15.0	18.6	30.0	30.0	21.8	7.5	30.0	30.0	1	1		60.0	
1116+70.00	TO 1117+40.00	70.0	86.8	140.0	140.0	101.8	35.0	140.0	140.0	4	4		280.0	
1117+40.00	TO 1118+70.00	130.0	161.2	260.0	260.0	189.0	65.0	260.0	260.0	7	7		520.0	
1118+70.00	TO 1119+40.00	70.0	86.8	140.0	140.0	101.8	35.0	140.0	140.0	4	4		280.0	
1119+40.00	TO 1119+60.00	20.0	24.8	40.0	40.0	29.1	10.0	40.0	40.0	1	1		80.0	
1119+60.00	TO 1120+30.00	70.0	86.8	140.0	140.0	101.8	35.0	140.0	140.0	4	4		280.0	
1120+30.00	TO 1133+17.92	1,287.9	1,597.2	2,575.8	2,575.8	1,872.2	644.0	2,575.8	2,575.8	64	64		5,151.7	
1133+17.92	TO 1133+58.00	40.1	49.6	80.2	80.2	58.3	20.0	80.2	80.2	2	2		160.3	
1133+58.00	TO 1133+88.00	30.0	37.2	60.0	60.0	43.6	15.0	60.0	60.0	2	2		120.0	
1133+88.00	TO 1134+28.01	40.0	49.6	80.0	80.0	58.2	20.0	80.0	80.0	2	2		160.0	
1134+28.01	TO 1140+58.00	630.0	781.2	1,260.0	1,260.0	915.8	315.0	1,260.0	1,260.0	31	31		2,520.0	
1140+58.00	TO 1140+98.00	40.0	49.6	80.0	80.0	58.1	20.0	80.0	80.0	2	2		160.0	
1140+98.00	TO 1141+27.84	29.8	37.1	59.7	59.7	43.4	14.9	59.7	59.7	1	1		119.4	
SHEET TOTALS		32,903.3	34,386.0	55,460.3	55,460.3	40,309.2	13,865.1	55,460.3	55,460.3	1,386.5	1,386.5	72.0	110,920.6	72.0

FILE NAME =	USER NAME = swartzrw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
as:\pw_work\p\dot\swartzrw\02288358\077	560-shh-sch.dgn	DRAWN -	REVISED -		SCALE: NA	SHEET 3	OF 6	SHEETS	STA.	TO STA.	Coles	48	15
	PLOT SCALE = 50.0000' / 1" =	CHECKED -	REVISED -		CONTRACT NO. 74560								
	PLOT DATE = 1/31/2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								