

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0005		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	67	67		
20400800	FURNISHED EXCAVATION	CU YD	210	210		
20800150	TRENCH BACKFILL	CU YD	16	16		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30	30		
28100105	STONE RIPRAP, CLASS A3	SO YD	28	28		
28200200	FILTER FABRIC	SQ YD	28	28		
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	94	94		
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	67	67		
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SO YD	184	184		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	608	608		
40600300	AGGREGATE (PRIME COAT)	TON	24	24		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SO YD	64	64		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	532	532		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED. 20% STATE 0005		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	8	8		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	1366	1366		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	6085	6085		
44000400	GUTTER REMOVAL	FOOT	35	35		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	355	355		
44000600	SIDEWALK REMOVAL	SO FT	1366	1366		
44004250	PAVED SHOULDER REMOVAL	SO YD	74	74		
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	107	107		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	238	238		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	18	18		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	37	37		
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1		
50300225	CONCRETE STRUCTURES	CU YD	6.1	6.1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	610	610		

FILE NAME =	USER NAME = steffennk	DESIGNED -	REVISED -
et:\pov\work\pvidat\steffennk\d0289124\074566-sh1-soq.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
828	12RS-1	Effingham	37	4
CONTRACT NO. 74566			ILLINOIS FED. AID PROJECT	