

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	68	68		
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	40	40		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	1		
60107700	PIPE UNDERDRAINS 6"	FOOT	284	284		
60219000	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 8 GRATE	EACH	1	1		
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	2	2		
60263900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1		
60602500	CONCRETE GUTTER, TYPE A	FOOT	19	19		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	355	355		
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4	4		

SUMMARY OF QUANTITIES			TOTAL	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	339	339		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	4		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	8		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	422	422		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	70	70		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3964	3964		

24 \* SPECIALTY ITEM

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -
c:\pwwork\pwwork\staffennk\d0289124\074566-sh1-soq.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
SCALE: NA SHEET 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
828	12RS-1	Effingham	37	5
CONTRACT NO. 74566				
ILLINOIS FED. AID PROJECT				