

GENERAL NOTES

THIS PROJECT IS LOCATED AT 12 SEPARATE LOCATIONS ON FAP 322 (US ROUTE 51). THERE ARE 6 INTERSECTIONS AROUND THE VILLAGE OF MOWEAQUA IN SHELBY COUNTY. THERE ARE 3 INTERSECTIONS AROUND THE CITY OF MACON AND 3 INTERSECTIONS AROUND THE CITY OF MAROA BOTH IN MACON COUNTY. THIS PROJECT CONSISTS OF STRIPING AT ALL 12 INTERSECTIONS AND FLASHING STOP SIGNS AND SPEED LIMIT SIGNS INSTALLED AT 1 INTERSECTION IN MOWEAQUA, 2 INTERSECTIONS IN MACON AND 2 INTERSECTIONS IN MAROA AND ALL OTHER WORK NECESSARY TO COMPLETE THIS PROJECT.

THE LOCATIONS OF THE FLASHING COMPONENTS AS SHOWN ON THE PLANS ARE APPROXIMATE ONLY. THE FINAL LOCATIONS SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.

THE EXISTING UTILITY LINES ARE SHOWN ON THE PLANS TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATION. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO BEGINNING CONSTRUCTION. CALL J.U.L.I.E. AT 1-800-892-0123.

THE TRAFFIC SIGNAL ENGINEER AT THE ILLINOIS DEPARTMENT OF TRANSPORTATION SHALL BE NOTIFIED AT 217-342-8382 AT LEAST 72 HOURS PRIOR TO TURNING ON ANY FLASHER OR CONTROLLER UNIT.

THE SIZE OF THE CABLE SUPPLIED SHALL BE EQUAL TO OR GREATER THAN THE SIZE OF THE CALBE REQUIRED TO CARRY THE LOAD BETWEEN THE CONTROLLER AND THE SERVICE INSTALLATION.

ALL HARDWARE SHALL BE TIGHENED AND WELL SECURED. CABLES SHALL BE NEATLY WOUND IN THE GULFBOXES. CABLES SHALL BE NEATLY TRAINED IN THE CONTROLLER CABINET.

NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR PLACING CONDUIT AT GREATER THAN 2 FOOT MINIMUM DEPTH TO AVOID OBXTACLES SUCH AS UNDERGROUND UTILITIES.

THE CONTRACTOR IS RESPONSIBLE FOR UNCOVERING OR HAND DIGGING AROUND UTILITIES AS NECESSARY.

THE NUMBER OF CONDUCTORS FOR ELECTRIC CABLES AS SHOWN ON THE PLANS SHALL BE THE MINIMUM NUMBER OF CONDUCTORS FURNISHED FOR EACH LOCATION. THE CONTRACTOR MAY SUBSTITUTE AN ELECTRIC CABLE WITH MORE CONDUCTORS THAT SPECIFIED BT NO ADDITIONAL COMPENSATION WILL BE MADE FOR THE EXTRA CONDUCTORS.

ALL NEW SIGNAL WIRING SHALL EXTEND FROM CONTROLLER TO SIGNAL. SPLICES IN HANDHOLESOR GULFBOXES WILL NOT BE ALLOWED.

KNOWN UTILITIES LOCATED WITHIN THE LIMITS OF THIS IMPROVEMENT ARE:

AMEREN-CIPS  
420 NORTH 2400 EAST RD  
PANA, IL 62557  
PH. 217-562-1439

SUDDENLINK COMMUNICATIONS  
127 S. MAIN  
MOWEAQUA, IL 62550

CITY OF MACON  
285 SOUTH FRONT ST.  
P.O. BOX 349  
MACON, IL 62544-0349  
PH. 217-764-3643

AMEREN/DIVISION IV GAS  
711 S. 9TH. ST.  
MATTOON, IL 61938  
PH. 217-234-0429

AMEREN-IP  
2400 NORTH JASPER STREET  
DECATUR, IL 62526  
217-424-7075

ALMEGA COMMUNICATIONS  
1204 S. SECOND ST  
GILLESPIE, IL 62033

VERIZON  
330 W. BEECHER  
JACKSONVILLE, IL 62650

CITY OF MAROA  
P.O. BOX 136  
MAROA, IL 61756

SHELBY ELECTRIC COOPERATIVE  
RTE 128 & N. SIXTH STREET  
P. O. BOX 560  
SHELBYVILLE, IL 62565  
217-774-3986

FRONTIER COMMUNICATIONS  
117 W. JEFFERSON  
MT. PULASKI, IL 62548  
217-792-0205

A T & T  
2250 N. JASPER  
DECATUR, IL 62526  
217-429-8596

VILLAGE OF MOWEAQUA  
122 NORTH MAIN ST.  
MOWEAQUA, IL 62550  
217-768-3435

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS AND GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 OVERALL LAYOUT-VILLAGE OF MOWEAQUA
- 5 LOCATION #4 SIGN LAYOUT
- 6-8 STRIPING DETAILS-VILLAGE OF MOWEAQUA
- 9 OVERALL LAYOUT-CITY OF MACON
- 10 LOCATION #8 & #9 CITY OF MACON
- 11-12 STRIPING DETAILS-CITY OF MACON
- 13 OVERALL LAYOUT-CITY OF MAROA
- 14 LOCATION #10 & #11 CITY OF MAROA
- 15-16 STRIPING DETAILS-CITY OF MAROA
- 17 DETAILS
- 18-21 PAVEMENT MARKING DETAILS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 21:

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 701001-02 OFF-ROAD OPERATIONS 2L, 2W, 15' MIN. AWAY
- 701006-03 OFF-ROAD OPERATIONS 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
- 701011-02 OFF-ROAD MOVING OPERATIONS 2L, 2W DAY ONLY
- 701101-02 OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
- 701106-02 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
- 701301-04 LANE CLOSURE 2L, 2W SHORT TIME OPERATIONS
- 701701-08 URBAN LANE CLOSURE MULTILANE INTERSECTION
- 701901-02 TRAFFIC CONTROL DEVICES
- 720001-01 SIGN PANEL MOUNTING DETAILS
- 805001-01 ELECTRICAL SERVICE INSTALLATION DETAILS
- 880001-01 SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION

701400-05  
701400-06

FILE NAME =	USER NAME = maelellanle	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS &amp; GENERAL NOTES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\puidot\mae\lellanle\d0296830	774568-sht-index-gn.dgn	DRAWN -	REVISED -			322	D7 SAFETY 2012-1	*	21	2	
PLOT SCALE = 100.0000 / in.		CHECKED -	REVISED -			CONTRACT NO. 74568					
PLOT DATE = 2/16/2012		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET OF SHEETS		STA.	TO STA.		