

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021 MACON CO	0021 SHELBY CO
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	310	310	
67100100	MOBILIZATION	L SUM	1	0.67	0.33
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	0.67	0.33
	701701				
72000200	SIGN PANEL - TYPE 2	SO FT	192	144	48
73000100	WOOD SIGN SUPPORT	FOOT	194	194	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	997	456	541
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4384	2121	2263
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2146	975	1171
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	8442	6755	1687
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	210	182	28
81500100	GULFBOX JUNCTION	EACH	25	21	4
85800100	FLASHER CONTROLLER	EACH	3	3	
87301125	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 3C	FOOT	13224	9779	3445

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021 MACON CO	0021 SHELBY CO
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2142	2142	
88040030	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	2	2	
89100400	ILLUMINATED SIGN, LED	EACH	8	6	2
X0326852	RADAR SPEED SIGN	EACH	8	6	2
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	310	310	
X7240195	REMOVE EXISTING SIGN PANEL	EACH	9	7	2
X7270025	REMOVE EXISTING SIGN SUPPORT	EACH	2		2
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	997	456	541
X8040102	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	3	3	

FILE NAME :	USER NAME : mcllellan	DESIGNED -	REVISED -
c:\pwork\puidot\mcllellan\d0296830\	774568-shr-soq.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / 1 in.	CHECKED -	REVISED -
	PLOT DATE = 2/16/2012	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS
		STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	D7 SAFETY 2012-1		21	3
CONTRACT NO. 74568			ILLINOIS FED. AID PROJECT	

• Macon, Shelby