

GUARDRAIL SCHEDULE

LOCATION STATION	TRAFFIC BARRIER TERMINAL		SPBGT TYPE A (6 FOOT POSTS)	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKER TYPE A	BARRIER WALL MARKER TYPE B
	TYPE 1 SPECIAL TANGENT	TYPE 6				
IL 146 (FAP 885)	EACH	EACH	FOOT	EACH	EACH	EACH
STA 1257+86.40 TO STA 1260+19.08						10
STA 1260+62.23 RT TO STA 1261+37.23 RT STA 1260+62.23 LT TO STA 1261+87.23 LT			75			
STA 1260+19.08 TO STA 1263+00.00			125		12	
NW QUAD	1	1		1		
NE QUAD		1			1	
SW QUAD	1	1		1		
SE QUAD		1			1	
TOTALS	2	4	200	2	14	10

PAVEMENT MARKING SCHEDULE

LOCATION STATION	TEMPORARY PAVEMENT MARKING LINE 4"	PAINT PAVEMENT MARKING LINE 4"
IL 146 (FAP 885)	FOOT	FOOT
STA 1254+70 TO STA 1263+48	878	
STA 1254+88 TO STA 1262+91	803	
STA 1256+27 RT TO STA 1261+92 RT	565	
STA 1256+40 LT TO STA 1262+55 LT	612	
STA 1256+87 LT TO STA 1260+42 LT		142
STA 1256+87 RT TO STA 1260+82 RT		395
STA 1256+87 TO STA 1263+00		1226
STA 1260+42 LT TO STA 1263+00 LT		258
STA 1260+82 RT TO STA 1263+00 RT		87
TOTALS	2858	2108

SEEDING SCHEDULE

LOCATION STATION	SEEDING CLASS 2	NITROGEN	PHOSPHOROUS	POTASSIUM	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING
IL 146 (FAP 885)	ACRE	LBS	LBS	LBS	TON	ACRE	POUND
NW QUAD	0.05	5	5	5	0.1	0.05	5
SW QUAD	0.1	9	9	9	0.2	0.1	10
NE QUAD	0.05	5	5	5	0.1	0.05	5
SE QUAD	0.05	5	5	5	0.1	0.05	5
TOTALS	0.25	24	24	24	0.5	0.25	25

EARTHWORK SCHEDULE

LOCATION STATION	*EARTH EXCAVATION	CHANNEL EXCAVATION	SHRINKAGE FACTOR FOR EARTH EXCAVATION	EARTH EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	**EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION
IL 146 (FAP 885)	CU YD	CU YD	%	CU YD	CU YD	CU YD	CU YD
STA 1256+50 TO STA 1258+88	18		25	5	15	-10	10
STA 1258+76 TO STA 1258+98		67	25				
STA 1259+88 TO STA 1263+00	32		25	8	106	-98	98
TOTALS	50	67		13	121	-108	108

* CUTS FROM CROSS SECTIONS
 ** FILLS FROM CROSS SECTIONS

FILE NAME = c:\pwworkh\pwworkh\plotted\146\146.dwg

USER NAME = \$USER\$	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
PLOT DATE = 2/2/2012	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	6B-2	POPE	51	11
CONTRACT NO., 78168			ILLINOIS FED. AID PROJECT	