

GENERAL NOTES

GENERAL NOTES

1. SEE CROSS SECTION FOR SPECIAL DITCHES AND BACK SLOPES.
2. THE REMOVAL AND DISPOSAL OF EXISTING SURFACE UNSUITABLE FOR USE IN CONJUNCTION OF CREATING A LEVEL SURFACE PRIOR TO THE PLACEMENT OF HMA SHALL BE REMOVED. AGGREGATE SHOULDERS SHALL BE PLACED AS AGGREGATE BASE COURSE, TYPE B (SPECIAL).
3. NO EXTRA COMPENSATION WILL BE ALLOWED FOR ROCK OR HAUL ROADS USED FOR TEMPORARY ACCESS TO THE SITE FOR CONTRACTOR'S WORK. ANY TEMPORARY ACCESSES FOR CONSTRUCTION SHALL BE WITHIN THE ALLOWABLE EASEMENT LIMITS AND CONSTRUCTION STAGING AREAS DESIGNATED ON THE PLANS. ALL COSTS ASSOCIATED WITH THIS WORK SHALL BE INCLUDED IN THE PAY ITEM FOR EARTH EXCAVATION. SPECIFIC REQUESTS MUST BE MADE IN WRITING PRIOR TO CREATING TEMPORARY ACCESS ROADS.
4. THE FINAL TOP SIX INCHES OF SOIL IN ANY RIGHT-OF-WAY AREA DISTURBED BY THE CONTRACTOR MUST BE CAPABLE OF SUPPORTING VEGETATION. THE SOIL MUST BE FROM THE A HORIZON (ZERO TO 4" DEEP) OF SOIL PROFILES OF LOCAL SOIL.
5. WHEN EMULSIFIED ASPHALT IS APPLIED, IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO COVER OR PROTECT ALL TRAFFIC SIGNS AND GUARDRAILS. ANY SIGNS AND GUARD RAILS WHICH BECOME COVERED WITH ASPHALTIC MATERIAL SHALL BE CLEANED BY THE CONTRACTOR AT HIS OWN EXPENSE.
6. MULCH ON TEMPORARY SEEDING SHALL BE MULCH METHOD 2. MULCH ON PERMANENT SEEDING SHALL BE MULCH METHOD 2, PROCEDURES 1, 2, OR 3.
7. CONTRACTOR SHALL COORDINATE FINAL LOCATION OF CHAIN LINK FENCE PRIOR TO INSTALLATION.
8. ALL EMBANKMENT CONSTRUCTED OF COHESIVE SOIL SHALL BE CONSTRUCTED WITH NOT MORE THAN 110% OF OPTIMUM MOISTURE CONTENT, DETERMINED BY THE STANDARD PROCTOR TEST. COHESIVE SOIL SHALL BE DEFINED AS ANY SOIL WHICH CONTAINS GREATER THAN 10% PARTICLES BY WEIGHT PASSING THE #200 SIEVE.
9. ANY PINS OR SURVEY MARKERS DAMAGED DURING CONSTRUCTION SHALL BE REPLACED BY A PROFESSIONAL ILLINOIS LAND SURVEYOR AT THE CONTRACTORS EXPENSE.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE JULIE NUMBER IS 800-892-0123. THESE UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS ARE MEMBERS OF JULIE.

AT&T 635 18TH ST. ROCK ISLAND, IL 61201 (309)793-4464	MID AMERICAN ENERGY 2811 5TH AVE. ROCK ISLAND, IL 61201 (309)793-3652	MEDIACOM 3900 26TH AVE. MOLINE, IL 61265 (309)743-4757	VILLAGE OF MILAN SEWER & WATER VILLAGE HALL, 405 E. 1ST ST. MILAN, IL 61264 (309)787-8530
--	--	---	--

THESE ARE THE KNOWN UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS WHICH ARE NOT MEMBERS OF JULIE AND SHOULD BE NOTIFIED INDIVIDUALLY BY THE CONTRACTOR.

11. THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES.

GRANULAR MATERIAL	2.05 TONS/C.Y.
BITUMINOUS MATERIALS PRIME COAT	0.10 GAL/S.Y.
BITUMINOUS CONCRETE SURFACE COURSE	112 LB/S.Y./INCH
TEMPORARY EROSION CONTROL SEEDING	100 LBS/ACRE
12. IT IS ESTIMATED THAT 49 CUBIC YARDS OF SUITABLE EARTH EXCAVATION WILL BE USED ON THE PROJECT SITE. A SHRINKAGE FACTOR OF 25% HAS BEEN USED. IT IS ESTIMATED THAT THIS MATERIAL WILL BE SUITABLE USE FOR FURNISHED EXCAVATION. IT IS ESTIMATED THAT AN ADDITIONAL 320 CUBIC YARDS OF FURNISHED EXCAVATION WILL BE REQUIRED FOR CONSTRUCTION.
13. ALL ELEVATIONS ARE REFERRING TO U.S.G.S. MEAN SEA LEVEL DATUM.
14. ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT-OF-WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.
15. ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUB-NUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

DATE	
BY	
FINAL SURVEY NOTE BOOK NO.	
DESIGNED	
DRAWN	
CHECKED	
DATE	

DATE	
BY	
ORIGINAL SURVEY NOTE BOOK NO.	
DESIGNED	
DRAWN	
CHECKED	
DATE	

FILE NAME =	USER NAME =	DESIGNED --	REVISED --
		DRAWN -- MPK	REVISED --
		CHECKED -- MKM	REVISED --
		DATE -- 2.14.12	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00043-00-BT	ROCK ISLAND	31	4
SCALE:			SHEET NO. 1 OF 1 SHEETS STA. TO STA.	
ILLINOIS FED. AID PROJECT				

CONTRACT NO. 85556