

C.H. 13 EARTHWORK TOTALS				
LOCATION	EARTH EXCAVATION (SPECIAL) X2020410*	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	FURNISHED EXCAVATION 20400800
	CU YD	CU YD	CU YD	CU YD
TOTAL	3,412	2,559	7,871	4,565

TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
STATION	UNIT	REMARKS
CH 13		
18+74 RT 46'	10	
PROJECT TOTAL	10	

TREE REMOVAL, ACRES		
STATION	ACRE	REMARKS
CH 13		
LT 20+16 TO 22+26	0.12	
PROJECT TOTAL	0.12	

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		
STATION	CU YD	REMARKS
CH 13		
CONTINGENCY ITEM	340	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	340	

TRENCH BACKFILL		
STATION	CU YD	REMARKS
CH 13		
10+43	62	48" P CUL
PROJECT TOTAL	62	

EROSION CONTROL BLANKET		
STATION	SQ YD	REMARKS
CH 13		
LT 9+50 TO 19+45	3,685	
RT 9+50 TO 20+20	2,959	
LT 20+20 TO 29+50	2,512	
RT 20+55 TO 29+50	2,899	
PEL 23+25	1,637	
PROJECT TOTAL	13,692	

TURF REINFORCEMENT MAT		
STATION	SQ YD	REMARKS
CH 13		
LT 9+50 TO 10+37	84	8' WIDE
RT 9+50 TO 12+63	291	8' WIDE
LT 10+64 TO 13+13	229	8' WIDE
RT 13+22 TO 16+50	308	8' WIDE
LT 13+52 TO 19+00	507	8' WIDE
LT 20+22 TO 23+02	875	
LT 23+44 TO 29+50	583	8' WIDE
RT 24+00 TO 27+16	287	8' WIDE
PROJECT TOTAL	3,164	

TEMPORARY EROSION CONTROL SEEDING		
STATION	POUND	REMARKS
CH 13		
LT 9+50 TO 19+45	93	100 LB / ACRE
RT 9+50 TO 20+20	74	100 LB / ACRE
LT 20+20 TO 29+50	82	100 LB / ACRE
RT 20+55 TO 29+50	66	100 LB / ACRE
PEL 23+25	34	100 LB / ACRE
PROJECT TOTAL	349	

TEMPORARY DITCH CHECKS		
STATION	FOOT	REMARKS
CH 13		
LT 10+00	17	
LT 11+00	13	
LT 11+50	20	
LT 12+50	13	
LT 15+00	14	
LT 15+50	12	
LT 16+00	14	
LT 16+50	17	
LT 17+00	23	
LT 17+50	28	
LT 18+00	13	
LT 18+50	13	
LT 24+00	16	
LT 24+50	24	
LT 25+00	23	
LT 25+50	14	
LT 26+00	14	
LT 29+00	13	
RT 11+00	17	
RT 12+00	11	
RT 13+50	9	
RT 14+00	20	
RT 14+50	18	
RT 15+00	19	
RT 15+50	21	
RT 16+00	20	
RT 16+50	13	
RT 24+00	19	
RT 24+50	19	
RT 25+00	14	
RT 25+50	14	
RT 26+00	8	
PROJECT TOTAL	523	

PERIMETER EROSION BARRIER		
STATION	FOOT	REMARKS
CH 13		
RT 16+50 TO 20+25	381	ALONG PROP ROW
LT 17+50 TO 19+34	187	ALONG PROP ROW
LT 20+15 TO 21+67	362	
RT 20+61 TO 24+00	339	ALONG PROP ROW
PROJECT TOTAL	1,269	

INLET AND PIPE PROTECTION		
STATION	EACH	REMARKS
CH 13		
10+37 RT 35'	1	AT DITCH INLET, SPECIAL
23+44 LT 40'	1	AT 24" P CUL
PROJECT TOTAL	2	

FILE : S:\S:\p\c\1156008\ch13\lasalle\plans\SCD General Notes.dgn



DESIGNED - J.M.K.
 CHECKED - G.F.S.
 DRAWN - J.M.K.
 CHECKED - G.F.S.

REVISED -
 REVISED -
 REVISED -
 REVISED -

LASALLE COUNTY
C.H. 13 OVER TOMAHAWK CREEK
STATION 20+00

SCHEDULE OF QUANTITIES
STRUCTURE NO. 050-3604
 SHEET NO. 1 OF 4 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
260	10-00651-00-BR	LASALLE	51	04
	WHA* 1156D08		CONTRACT NO. 87466	
ILLINOIS FED. AID PROJECT BRS-0260105				