

GRATING FOR CONCRETE FLARED END SECTION 48"		
STATION	EACH	REMARKS
CH 13		
LT 10+50	1	
PROJECT TOTAL	1	

STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS		
STATION	FOOT	REMARKS
CH 13		
LT 18+42.97 TO 18+92.97	50	
RT 17+61.44 TO 19+11.44	150	
LT 20+88.56 TO 22+38.56	150	
RT 21+07.03 TO 21+57.03	50	
PROJECT TOTAL	400	

TRAFFIC BARRIER TERMINAL, TYPE 6		
STATION	EACH	REMARKS
CH 13		
LT 18+92.97 TO 19+36.12	1	
RT 19+11.44 TO 19+54.59	1	
LT 20+45.41 TO 20+88.56	1	
RT 20+63.88 TO 21+07.03	1	
PROJECT TOTAL	4	

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		
STATION	EACH	REMARKS
CH 13		
LT 17+92.97 TO 18+42.97	1	
RT 17+11.44 TO 17+61.44	1	
LT 22+38.56 TO 22+88.56	1	
RT 21+57.03 TO 22+07.03	1	
PROJECT TOTAL	4	

GUARDRAIL REMOVAL		
STATION	FOOT	REMARKS
CH 13		
RT 15+28.26 TO 19+80.30	453	
LT 18+90.07 TO 19+65.16	75	
LT 20+20.08 TO 21+43.39	124	
RT 20+34.48 TO 24+14.52	379	
PROJECT TOTAL	1,031	

FURNISHING & ERECTING RIGHT-OF-WAY MARKERS		
STATION	EACH	REMARKS
CH 13		
9+50.00 LT 35.00'	1	
10+00.00 LT 55.00'	1	
12+21.96 LT 48.03'	1	
17+01.62 LT 50.00'	1	
17+50.00 LT 50.00'	1	
19+00.00 LT 80.00'	1	
20+13.14 LT 219.34'	1	
20+21.21 LT 80.00'	1	
24+47.25 LT 68.93'	1	
26+00.00 LT 45.00'	1	
27+94.70 LT 45.00'	1	
29+00.00 LT 45.00'	1	
29+50.00 LT 35.00'	1	
10+00.00 RT 35.00'	1	
10+50.00 RT 45.00'	1	
15+00.00 RT 45.00'	1	
15+50.00 RT 50.00'	1	
19+00.00 RT 50.00'	1	
19+50.00 RT 75.00'	1	
21+00.00 RT 75.00'	1	
21+50.00 RT 60.00'	1	
22+94.69 RT 60.00'	1	
23+50.00 RT 50.00'	1	
26+00.00 RT 50.00'	1	
26+50.00 RT 35.00'	1	
		ALL MARKERS METHOD A UNLESS NOTED
PROJECT TOTAL	25	

PERMANENT SURVEY MARKERS, TYPE I		
STATION	EACH	REMARKS
CH 13		
	1	WINGWALL - AS DIRECTED BY ENGINEER
PROJECT TOTAL	1	

PAINT PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
CH 13		
9+50 TO 29+50	4000	DOUBLE YELLOW CENTERLINE
LT 9+50 TO 29+50	2,000	WHITE EDGELINE
RT 9+50 TO 29+50	2,000	WHITE EDGELINE
		WORK TO BE DONE BY LCHD.
PROJECT TOTAL	8,000	

GUARDRAIL MARKERS, TYPE A		
STATION	EACH	REMARKS
CH 13		
LT 17+92.97 TO 19+36.12	4	BIDIRECTIONAL SILVER / SILVER
LT 20+45.41 TO 22+88.56	4	BIDIRECTIONAL SILVER / SILVER
RT 17+11.44 TO 19+54.59	4	BIDIRECTIONAL SILVER / SILVER
RT 20+63.88 TO 22+07.03	4	BIDIRECTIONAL SILVER / SILVER
PROJECT TOTAL	16	

GUARDRAIL MARKERS, TYPE B		
STATION	EACH	REMARKS
CH 13		
LT 19+36.12 TO 20+45.41	4	BIDIRECTIONAL SILVER / SILVER
RT 19+54.59 TO 20+63.88	4	
PROJECT TOTAL	8	

TERMINAL MARKER - DIRECT APPLIED		
STATION	EACH	REMARKS
CH 13		
LT 17+92.97	1	
RT 17+11.44	1	
LT 22+88.56	1	
RT 22+07.03	1	
PROJECT TOTAL	4	

TUBULAR STEEL GATE		
STATION	EACH	REMARKS
CH 13		
PEL 23+25	1	
PROJECT TOTAL	1	

TEMPORARY FENCE (SPECIAL)		
STATION	FOOT	REMARKS
CH 13		
LT 19+62 TO 21+53	235	
RT 16+79 TO 20+39	365	
RT 20+59 TO 24+00	340	
PROJECT TOTAL	940	

FILE = S:\SAS\Project\11560\06\Ben\13\esol\1a\Plans\S00\_General\_Notes.dgn



DESIGNED - J.M.K.	REVISED -
CHECKED - G.F.S.	REVISED -
DRAWN - J.M.K.	REVISED -
CHECKED - G.F.S.	REVISED -

**LASALLE COUNTY**  
**C.H. 13 OVER TOMAHAWK CREEK**  
**STATION 20+00**

**SCHEDULE OF QUANTITIES**  
**STRUCTURE NO. 050-3604**  
 SHEET NO. 3 OF 4 SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
260	10-00651-00-BR	LASALLE	51	06
	WHA* 1156D08		CONTRACT NO. 87466	
ILLINOIS FED. AID PROJECT BRS-0260105				