

PAVEMENT MARKING SCHEDULE							
LOCATION	TEMPORARY		PAINT PAVEMENT MARKING		SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
			PERMANENT				
	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE			
	70300220	70300220	78001110	78001110	70300100	70301000	78300100
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT
FAS 7043/CH6							
LT. STA 13+80 TO LT. STA 21+25	745		745			248	248
RT. STA 13+80 TO RT. STA 21+25	745		745			248	248
CL. STA 13+80 TO LT. STA 21+25		186		186	20	62	62
SUBTOTAL	1490	186	1490	186	20	558	558
TOTAL	1676		1676		20	558	558

EARTHWORK SUMMARY							
LOCATION	EARTH EXCAVATION	CHANNEL EXCAVATION	SHRINKAGE FACTOR	% USED	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE(25%)	EMBANKMENT REQUIRED	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	20200100 CUBIC YARD	20300100 CUBIC YARD				CUBIC YARD	CUBIC YARD
FAU 7043/ CH6							
STAGE 1							
STA 14+85 TO STA 16+81.88	65		25.00%	100.00%	49	15	34
STA 18+18.13 TO STA 20+00	67		25.00%	100.00%	50	22	28
STAGE 2							
STA 14+85 TO STA 16+81.88	2		25.00%	100.00%	2	20	-18
STA 18+18.13 TO STA 20+00	8		25.00%	100.00%	6	56	-50
FROM BRIDGE BILL OF MATERIALS		500			0		0
	142	500			107	113	-6
	FURNISHED EXCAVATION					6	CU.YD.

STAGING SCHEDULE					
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY BRIDGE TRAFFIC SIGNALS	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	70400100	70400200	70106500	Z0030250	Z0030350
	FOOT	FOOT	EACH	EACH	EACH
FAS 7043/CH6					
STAGE I					
CL. STA 13+70 TO STA 21+35	350		1	2	
STAGE II					
CL. STA 13+70 TO STA 21+35		350			2
TOTAL	350	350	1	2	2

X2501000 SEEDING, CLASS 2 (SPECIAL)	
LOCATION	ACRE
FAU 7043/CH6	
LT. STA 15+25 TO LT. STA 16+81	0.05
RT. STA 14+85 TO RT. STA 16+81	0.06
LT. STA 18+18 TO LT. STA 20+00	0.07
RT. STA 18+20 TO RT. STA 19+50	0.03
TOTAL	0.21
TOTAL USE	0.25