SUMMARY OF QUANTITIES

					LEG 1	LEG 2	LEG 3	LEG 4
				STATION TO STATION	314+79 TO 319+77	100+00 TO 114+35	199+56 TO 214+36	400+00 TO 403+59
				DESCRIPTION	INSIDE US 150 R-O-W (CONNECTS BARBER PARK TO EXISTING PATHWAY)	ALONG LAKE OF WOODS RD FROM US 150 TO PEARL DRIVE	INSIDE LAKE OF WOODS FOREST PRESERVE FROM ELKS LAKE TO MAIN ENTRANCE	INSIDE LAKE OF WOODS FOREST PRESERVE NORTH PATH UP TO HEADQUARTERS
				FUNDING	80/20	80/20	80/20	80/20
				LENGTH IN FEET	497	1,435	1,480	359
	ITEM NUMBER	ITEM NAME	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	122.0		63.0	34.0	25.0
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	106.0			52.0	54.0
	20100500	TREE REMOV ACRES	ACRE	0.2	0.035		0.140	0.025
	20200100	EARTH EXCAVATION	CU YD	394.0	22.0	173.0	182.0	17.0
	20400800	FURNISHED EXCAVATION	CU YD	452.0	202.0		250.0	
	20800150	TRENCH BACKFILL	CU YD	210.0	0.2	186.0	23.8	
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,353.0	185.0	659.0	426.0	83.0
Δ	25000200	SEEDING, CLASS 2	ACRE	2.2	0.5	0.8	0.8	0.1
Δ	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	198.0	45.0	72.0	72.0	9.0
Δ	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	198.0	45.0	72.0	72.0	9.0
Δ	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	198.0	45.0	72.0	72.0	9.0
Δ	25100125	MULCH, METHOD 3	ACRE	2.2	0.5	0.8	0.8	0.1
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	220.0	50.0	80.0	80.0	10.0
	28000305	TEMPORARY DITCH CHECKS	FOOT	20.0		10.0	10.0	
	28000400	PERIMETER EROSION BARRIER	FOOT	520.0	435.0	15.0	70.0	
	28000500	INLET AND PIPE PROTECTION	EACH	12.0	1.0	8.0	3.0	
	28000510	INLET FILTERS	EACH	1.0		1.0		
	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	80.0		80.0		
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	109.0		101.0	8.0	
*	40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	428.0		397.0	31.0	
	42400300	PCC SIDEWALK 6 INCH	SQ FT	33,284.0	4,688.0	13,388.0	11,473.0	3,735.0
	42400410	PCC SIDEWALK 8 INCH	SQ FT	4,838.0		1,238.0	3,600.0	
*	X4240440	PCC SIDEWALK 6 INCH SPECIAL	SQ FT	1,875.0	1,875.0			
	42400800	DETECTABLE WARNINGS	SQ FT	188.0		108.0	40.0	40.0
	44000100	PAVEMENT REMOVAL	SQ YD	1,551.0		450.0	1,101.0	
	44000600	SIDEWALK REMOVAL	SQ FT	216.0		216.0		
	50105220	PIPE CULVERT REMOVAL	FOOT	393.0		296.0	97.0	
	542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	65.0			65.0	
	542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	75.0	47.0		28.0	
	542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	98.0		46.0	52.0	
*	54213447	END SECTIONS 12"	EACH	4.0	2.0		2.0	
*	54213453	END SECTIONS 18"	EACH	4.0		2.0	2.0	
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	767.0		767.0		
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	148.0		148.0		
Δ *	56109210	WATER VALVES TO BE ADJUSTED	EACH	1.0		1.0		
Δ *	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1.0		1.0		
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1.0		1.0		
	60100925	PIPE DRAINS 8"	FOOT	106.0		106.0		
	60221700	MANHOLES, TYPE A, 5' DIA, TY 8 GR	EACH	1.0		1.0		
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1.0		1.0		
	60240301	INLETS, TYPE B, 8 GRATE	EACH	5.0		5.0		
	67100100	MOBILIZATION	L SUM	1.0	0.2	0.4	0.4	
*	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	0.1	0.7	0.2	
	72000100	SIGN PANEL - TYPE 1	SQ FT	64.0			43.65	20.35
	72900100	METAL POST - TYPE A	FOOT	216.0			144.0	72.0
Δ	78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	63.0		63.0		
Δ	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	190.0		190.0		
Δ	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	24.0		24.0		
*	Z0077800	WOOD POST	EACH	16.0	2.0		12.0	2.0
*	X0350805	FOLD DOWN BOLLARDS	EACH	4.0	1.0		2.0	1.0
*	X0327301	RELOCATE EXISTING MAILBOX	EACH	3.0		3.0		
*	Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	1.0		1.0		
Δ *	A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CAL., B&B	EACH	6.0	2.0		4.0	
Δ *	A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CAL., B&B	EACH	4.0			4.0	
Δ *	B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CAL, TREE FORM, B&B	EACH	4.0			4.0	

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

REVISION	DATE	DESCRIPTION

PROJECT TITLE
VILLAGE OF MAHOMET & CC FOREST PRESERVE
LAKE OF THE WOODS ROAD
MULTI-PURPOSE PATHWAY

SHEET TITLE
SUMMARY OF QUANTITIES

Sodemann and Associates, Inc.
340 NORTH NEIL STREET
POST OFFICE BOX 537
CHAMPAIGN, ILLINOIS 61824-0537
TEL 217 352-7688 FAX 217 352-7922
ENGINEERING / ANALYSIS / MANAGEMENT

DES. CMD
DRN. MSD
CHK. EBM
APP. SRS

PROJECT NO. 10109

DATE 12-12-2011

SHEET 5 OF 64 SHEETS