

CODE NO.	PAY ITEM	UNIT	0031 ITEP/LOCAL FUNDS	0031 LOCAL FUNDS	TOTAL
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	140		140
* 28000500	INLET AND PIPE PROTECTION	EACH	17		17
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50		50
* 42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	104		104
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	6666		6666
42400800	DETECTABLE WARNINGS	SQ FT	396		396
44000100	PAVEMENT REMOVAL	SQ YD	104		104
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	524		524
44000600	SIDEWALK REMOVAL	SQ FT	6666		6666
* 31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	43		43
△* 56109210	WATER VALVES TO BE ADJUSTED	EACH	1		1
△* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1		1
* 60255500	MANHOLES TO BE ADJUSTED	EACH	3		3
* 60260100	INLETS TO BE ADJUSTED	EACH	4		4
* 60603800	COMBINATION CURB AND GUTTER, TYPE B-6.12	FOOT	69		69
* 60604400	COMBINATION CURB AND GUTTER, TYPE B-6.18	FOOT	455		455
67100100	MOBILIZATION	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60		60
△ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	28		28
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	79		79
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2041		2041
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	390		390
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	2899		2899
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
△* C2007224	SHRUB, ROSA KNOCKOUT (KNOCKOUT ROSE), 24" HEIGHT, CONTAINER	EACH	12		12
△* C2011624	SHRUB, VIBURNUM CARLESI (KOREANSPICE VIBURNUM), 2' HEIGHT, BALLED AND BURLAPPED	EACH	10		10
△* C2C05824	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2' WIDTH, CONTAINER	EACH	18		18
△* K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	5.34		5.34
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
* X7240505	RELOCATE SIGN PANEL AND POST	EACH	20		20
△* X8140105	HANDHOLE (SPECIAL)	EACH	2		2
△* XX007152	DECORATIVE LIGHT POLE, ALUMINUM, 12' MOUNTING HEIGHT	EACH	61		61
△* XX008270	BANNER ARMS	EACH		57	57
△* XX004977	FLAG POLE INSERT	EACH		61	61
* XX006616	LANDSCAPE REMOVAL	EACH	111		111
△* XX007472	ORNAMENTAL GRASSES	UNIT	4.36		4.36
△* XX008661	CLEANOUTS TO BE ADJUSTED	EACH	1		1
△* XX008662	REMOVE EXISTING LIGHT POLE	EACH	120		120

△ SPECIALTY ITEM
* SPECIAL PROVISION

**EFFINGHAM DOWNTOWN
STREETSCAPE**

**CITY OF EFFINGHAM
EFFINGHAM COUNTY**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

DRAWN BY
DRR
DATE
3/9/12
CHECKED BY
RDY

**Farnsworth
GROUP**
106 N. Second Street, Suite A
Effingham, Illinois 62401
217/342-5988, 217/342-5989 fax

FILE NO.
24-8575
BOOK NO.
SHEET NO.
2 OF 59