

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	705
40600300	AGGREGATE (PRIME COAT)	TON	20
40600990	TEMPORARY RAMP	SQ YD	223
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1410
42400800	DETECTABLE WARNINGS	SQ FT	310
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1549
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	10071
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	332
44000600	SIDEWALK REMOVAL	SQ FT	1365
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	332
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	942
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6909
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	113
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	20
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2504
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6909
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	113
△ 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	20
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

△ SPECIALTY ITEMS

FILE NAME = combschedulesKeebler.dgn	USER NAME = remesh	DESIGNED - BFK	REVISED -	VILLAGE OF MARYVILLE KEEBLER ROAD	QUANTITY SCHEDULES			F.A.U. RTE. 9135	SECTION 10-00018-00-RS	COUNTY MADISON	TOTAL SHEETS 22	SHEET NO. 3
		DRAWN - JJB	REVISED -		SCALE: N.T.S.	SHEET NO. 1 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 97486			
		CHECKED - BFK	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
		DATE - 1/17/12	REVISED -									