

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				80% FED 20% STATE ROADWAY 0005 FAS 733	80% FED 20% STATE ROADWAY 0005 FAP 310	100% STATE BRIDGE 0013 031-0029	100% STATE BRIDGE 0013 031-0030	100% STATE BRIDGE 0013 031-0031
				44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	20820	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1326	268	1058			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3263	713	2550			
50102400	CONCRETE REMOVAL	CU YD	0.8				0.8	
50105220	PIPE CULVERT REMOVAL	FOOT	516		516			
50300225	CONCRETE STRUCTURES	CU YD	3.9			1.3	1.5	1.1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	720			270	220	230
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	512		512			
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	5		5			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		1			
54248510	CONCRETE COLLAR	CU YD	0.2		0.2			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1			
60240395	INLETS, TYPE B	EACH	1		1			
60600605	CONCRETE CURB, TYPE B	FOOT	150			50	50	50

△

△ REV. 4-18-2018

FILE NAME =	USER NAME = leej	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
pin\1084EBIDINTEG.illinois.gov\PIDOT\Documents\DOT Office\District 5\Projects\0876\DRAWNData\0404\0876\31-shr-SD0.dwg		CHECKED -	REVISED -		310 733	(51-1,52-1,53,54,55)RS-4	GREENE	24	4				
Default	PLOT SCALE = 100.0000' / in.	DATE -	REVISED -		SCALE:	SHEET 2	OF 4 SHEETS	STA.	TO STA.	CONTRACT NO. 76K31			
	PLOT DATE = 1/29/2018									ILLINOIS FED. AID PROJECT			