

SCHEDULE OF QUANTITIES

SN	Facility Carried	Feature Crossed	Location	Length Total	Bridge Rdwy Width	Area to be Sealed [△]	Traffic Control Standard
0370003	FAI 74 & 280 EB	US6, BN RR, & TR38	1 MI SW GREEN ROCK	474.8	39	21,841	701400 & 701406 OR 701426
0370004	FAI 74 & 280 WB	US6, BN RR, & TR38	1 MI SW GREEN ROCK	442.6	39	20,360	701400 & 701406 OR 701426
0370015	FAI 74 SB	OPHIEM RD/FAS240	3 MI S JCT ILL 81	109.6	40	5,151	701400 & 701406 OR 701426
0370016	FAI 74 NB	OPHIEM RD/FAS240	3 MI S JCT ILL 81	109.6	40	5,151	701400 & 701406 OR 701426
0370017	FAI 74 SB	TR 379B	1 MI N JCT ILL 17	137.5	39	6,325	701400 & 701406 OR 701426
0370018	FAI 74 NB	TR 379B	1 MI N JCT ILL 17	137	41.4	6,631	701400 & 701406 OR 701426
0370021	FAI 80 SB	ROCK RIVER	AT ROCK ISLAND CO	1186.1	42	58,119	701400 & 701406 OR 701426
0370022	FAI 80 NB	ROCK RIVER	AT ROCK ISLAND CO	1186.1	42	58,119	701400 & 701406 OR 701426
0370023	FAI 80 SB	CLEVELAND RD/FAP595	2.1 M N JCT US 6	131.3	50.2	7,510	701400 & 701406 & 701411
0370024	FAI 80 NB	CLEVELAND RD/FAU5864	2.1 MI N JCT US 6	131.3	44.5	6,762	701400 & 701406 & 701411
0370027	I 80 SB	IAIS RR	1.7 MI N JCT US 6	158.6	40	7,454	701400 & 701406 OR 701426
0370028	FAI 80 NB	IAIS RR	1.7 MI N JCT US 6	158.6	40	7,454	701400 & 701406 OR 701426
0370031	FAI 80 SB	FAI 74	3 MI SE COLONA	274.2	51.9	16,150	701400 & 701406 & 701411
0370032	FAI 80 NB	FAI 74	3 MI SE COLONA	274.2	47.8	15,026	701400 & 701406 & 701411
0370064	FAP 22 / IL 78	FAI 80	N EDGE ANNAWAN	234	32.8	9,313	701400 & 701406 & 701411
0370066	ILL RT 92	PENNY SLOUGH	1.0 MI W JCT ILL 82	106.9	32	4,169	701201
0370080	ILL RT 84	GREEN RIVER	S EDGE COLONA	252	40.4	11,945	701201
0370100	ULAH ROAD	EDWARDS RIVER	1.2 MI S JCT ILL 81	105.2	20	2,840	701201
0370102	TR149	FAI 74	1.0 MI S JCT I80	224	24	6,944	701201
0370103	TR 169	FAI 74	3.0 MI S JCT FAI 80	224	24	6,944	701201
0370104	TR 251	FAI 74	2 MI. N. OF IL81	225	24	6,975	701201
0370109	TR 122	FAI 80	4.5 MI W OF GENESEO	225	24	6,975	701201
0370111	TR 172	FAI 80	1.0 MI W OF GENESEO	228	24	7,068	701201
0370112	TR 196-D	FAI 80	.34 MI E GENESEO	281	24	8,711	701201
0370113	TR 216	FAI 80	2.5 MI SE OF GENESEO	221	24	6,851	701201

MODEL: Default
 FILE: \\nas01\B&E\BID\NTEC\Illinois\gov\PIV\DOT\Documents\BID\DOT\Office\BID\BID\2\Projects\Operations\Bridges_Section\Bridges_Deck_Sealing_Contract\2018\64M87\CADD\02-04-18-shc-cov-er.dgn

USER NAME = dossed	DESIGNED - _____	REVISED - _____
	DRAWN - _____	REVISED - _____
PLOT SCALE = 100,0000' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = Apr-13-2018 09:43:49 AM	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D2 BDS 2018-3	HENRY	16	4
			CONTRACT NO. 64M87	
		ILLINOIS FED. AID PROJECT		

