



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 17, 2018

SUBJECT: FAP Route 860 (IL 31)
Project NHPP-Y1YJ(659)
Section 12R-RS-2
Kendall County
Contract No. 62C61
Item No. 152, April 27, 2018 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions
2. Revised page 53 of the Special Provisions
3. Deleted pages 54-58 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Acting Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Anthony Quigley, Region 1, District 1; Tim Kell

MS/ck

TABLE OF CONTENTS

LOCATION OF PROJECT.....	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS.....	2
CLEANING EXISTING DRAINAGE STRUCTURES	2
TRAFFIC CONTROL PLAN.....	2
ADJUSTMENTS AND RECONSTRUCTIONS	3
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1DISTRICT 1)	4
FRICITION AGGREGATE (D-1).....	6
RADING AND SHAPING SHOULDERS.....	9
GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1)	9
HMA MIXTURE DESIGN REQUIREMENTS (D-1).....	11
PUBLIC CONVENIENCE AND SAFETY (DIST 1)	18
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D-1)	18
TEMPORARY INFORMATION SIGNING.....	29
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY).....	30
ADJUSTING FRAMES AND GRATES (BDE)	31
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE).....	32
BUTT JOINTS (BDE).....	34
COMPENSABLE DELAY COSTS (BDE)	35
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	39
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	41
EQUIPMENT PARKING AND STORAGE (BDE)	52
HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE).....	52
HOT-MIX ASPHALT – TACK COAT (BDE).....	59
LIGHTS ON BARRICADES (BDE)	59
PAYMENTS TO SUBCONTRACTORS (BDE)	60
PORTLAND CEMENT CONCRETE (BDE)	60
PROGRESS PAYMENTS (BDE).....	61
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE).....	62
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	62
TEMPORARY PAVEMENT MARKING (BDE).....	63

b. Unconfined Edge. Each unconfined edge joint density shall be represented by an average of three one-minute density readings or a single core density at the given density test location and shall meet the density requirements specified herein. The three one-minute readings shall be spaced 10 ft (3 m) apart longitudinally along the unconfined pavement edge and centered at the random density test location.”

Revise the Density Control Limits table in Article 1030.05(d)(4) of the Standard Specifications to read:

“Mixture Composition	Parameter	Individual Test (includes confined edges)	Unconfined Edge Joint Density Minimum
IL-4.75	Ndesign = 50	93.0 – 97.4% ^{1/}	91.0%
IL-9.5	Ndesign = 90	92.0 – 96.0%	90.0%
IL-9.5,IL-9.5L	Ndesign < 90	92.5 – 97.4%	90.0%
IL-19.0	Ndesign = 90	93.0 – 96.0%	90.0%
IL-19.0, IL-19.0L	Ndesign < 90	93.0 ^{2/} – 97.4%	90.0%
SMA	Ndesign = 50 & 80	93.5 – 97.4%	91.0%”

Pages 54-58 have been deleted
 Then next page is 59

Revised 4/17/18