

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99-1-1-3	WILL	34	2
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT 60A42

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	SCHEDULE OF HIGH TENSION CABLE SYSTEM ITEMS
5-6	TYPICAL SECTIONS
7-20	EXISTING AND PROPOSED ROADWAY PLAN
21	TRAFFIC CONTROL FOR FREWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES
22-34	HIGH TENSION GUARDRAIL DETAILS (GIBALTAR)

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
630001-06	BITUMINOUS SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
701101-01	OFF-RD OPERATIONS, MULTILANE LESS THAN 4.5 M (15') AWAY FOR SPEEDS ≥ 45 MPH
701400-02	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-03	LANE CLOSURE, FREEWAY/EXPRESSWAY
702001-06	TRAFFIC CONTROL DEVICES

PLAN NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800)892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED.)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- THE CONTRACTOR SHALL CALL STATE ELECTRICAL CONTRACTOR AT (773) 287-7600 TO LOCATE STATE OWNED FACILITIES.
- THE PROPOSED DEPTH OF THE CONCRETE SOCKETED FOUNDATIONS AND END ANCHORAGE FOUNDATIONS AS SHOWN IN THE GIBALTAR DETAILS SHALL BE 42" (MINIMUM). THE FOUNDATION WORK SHALL BE INCLUDED IN THE COST OF THE HIGH TENSION CABLE MEDIAN SYSTEM.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">INTERSTATE 80 INDEX OF SHEETS LIST OF STATE STANDARDS PLAN NOTES</p> <p>SCALE: VERT. : NONE DRAWN BY: HMO HORIZ. : CHECKED BY: DATE</p>