

60A64

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		IL 50 @ 207th		Y031-3D		
				1000-1A 80% FED 20% STATE	Y031-1F 80% FED 10% STATE 10% VILLAGE			
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	121	121				
81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	135	135				
81400100	HANDHOLE	EACH	4	4				
81400200	HEAVY-DUTY HANDHOLE	EACH	4	4				
81400300	DOUBLE HANDHOLE	EACH	2	2				
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	759	759				
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	913	913				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1586	1586				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1162	1162				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1537	1537				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1600	1600				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	228	228				
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2	2				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2	2				
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1	1				
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1	1				
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2	2				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20	20				
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4	4				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60	60				
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8	8				
88500100	INDUCTIVE LOOP DETECTOR	EACH	8	8				
88600100	DETECTOR LOOP, TYPE I	FOOT	1166	1166				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		IL 50 @ 207th		Y031-3D		
				1000-1A 80% FED 20% STATE	Y031-1F 80% FED 10% STATE 10% VILLAGE			
88700200	LIGHT DETECTOR	EACH	2		2			
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1			
88800100	PEDESTRIAN PUSH-BUTTON	EACH	5	5				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103.4	103.4				
X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	1745	1745				
<del>X4066426</del>	<del>BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70</del>	<del>TON</del>	<del>22</del>	<del>22</del>				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	22	22				
X4066740	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N70	TON	15	15				
<del>X4066740</del>	<del>LEVELING BINDER (MACHINE METHOD) SUPERPAVE N70</del>	<del>TON</del>	<del>15</del>	<del>15</del>				
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2				
X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1		1			
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	737		737			
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	272		272			
X8800020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6		6			
X8800040	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2			
X8800045	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2		2			
X8800060	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2			
X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2		2			
X8810620	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	3		3			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1				
X0325252	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 15 1/2"	SQ. YD.	260	260				

\* SPECIALTY ITEM  
 Δ NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 2/10/2006

2/10/2006 2:10:06 PM