

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	125VBR-1	DEKALB	55	3
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	

Item No.	Item	Unit	Total QUANTITY	80% FED 20% STATE	
				1000 ROADWAY	X171-58 BRIDGE
20101000	TEMPORARY FENCING	FOOT	680	680	--
20200100	EARTH EXCAVATION	CU YD	23	23	--
20400800	FURNISHED EXCAVATION	CU YD	4	4	--
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	110	--	110
28000400	PERIMETER EROSION BARRIER	FOOT	400	400	--
28100105	STONE RIPRAP, CLASS A3	SQ YD	112	112	--
35100100	AGGREGATE BASE COURSE, TYPE A	TON	20	20	--
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	12	12	--
40500300	BITUMINOUS MIXTURE COMPLETE	TON	1974	1974	--
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.4	7.4	--
40600300	AGGREGATE (PRIME COAT)	TON	47	47	--
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	0.2	0.2	--
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	638	638	--
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	4	4	--
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222	222	--
42001300	PROTECTIVE COAT	SQ YD	222	222	--
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44	44	--
44000100	PAVEMENT REMOVAL	SQ YD	97	97	--
44000700	APPROACH SLAB REMOVAL	SQ YD	106	106	--
48101200	AGGREGATE SHOULDERS, TYPE B	TON	321	321	--
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	--	1
50200100	STRUCTURE EXCAVATION	CU YD	78	--	78
50300100	FLOOR DRAINS	EACH	12	--	12
50300225	CONCRETE STRUCTURES	CU YD	143.3	--	143.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	198.3	--	198.3
50300260	BRIDGE DECK GROOVING	SQ YD	545	--	545
50300300	PROTECTIVE COAT	SQ YD	718	--	718
50500305	ERECTING STRUCTURAL STEEL	L SUM	1	--	1
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	170	--	170
50500505	STUD SHEAR CONNECTORS	EACH	1674	--	1674
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	51970	--	51970
51100100	SLOPE WALL, 4 INCH	SQ YD	66	--	66
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	553	--	553
51201100	FURNISHING METAL PILE SHELLS 14"	FOOT	464	--	464
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	895	--	895
51202600	DRIVING AND FILLING SHELLS	FOOT	464	--	464
51202700	DRIVING STEEL PILES	FOOT	895	--	895
51203200	TEST PILE METAL SHELLS	EACH	1	--	1
51203600	TEST PILE STEEL HP 12X53	EACH	1	--	1
51500100	NAME PLATES	EACH	1	--	1
54205893	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL EQUIVALENT ROUND SIZE 18"	FOOT	9	9	--
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	61	--	61
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	128	--	128
60500060	REMOVING INLETS	EACH	4	4	--
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	100	100	--
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	--
* 63200310	GUARDRAIL REMOVAL	FOOT	200	200	--
* 63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	FOOT	487.5	487.5	--
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1	--
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	--
67100100	MOBILIZATION	L SUM	1	1	--
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	--
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122	122	--
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4480	4480	--
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	112	112	--
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	5	5	--
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2	--
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	2	2	--
78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2	--
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	57	57	--
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	TON	71	71	--
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1	--
Z0002600	BAR SPLICERS	EACH	64	--	64
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	--
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	--	1

\* SPECIAL

REVISIONS	
NAME	DATE
ARR	2/7/06
ARR	3/2/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 FAP 553 (IL 72)  
 SECTION 125VBR-1  
 DEKALB COUNTY

SCALE: VERT.  
 HORIZ.  
 DATE 11/05

DRAWN BY NQ  
 CHECKED BY JKC