

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	RS, R	**	302	3
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

* FAU 8239, FAS 1767, FAS 1766 & SBI 16 (OLD US 66)
 ** MONTGOMERY & MACOUPIN COUNTIES
CONTRACT NO. 72526

CODED NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY 80% FEDERAL 20% STATE	MONTGOMERY COUNTY						MACOUPIN COUNTY	
				TRAFFIC SIGNALS FAU 8239 - URBAN OLD US 66 & IL ROUTE 16 Y031-IF	ROADWAY FAU 8239 - URBAN BITUMINOUS RESURFACING NORTH PROJECT LIMITS TO STA 688+28.13 BK NB & SB STA 688+48.07 AH TO STA 690+15.7 NB & SB STA 690+15.7 TO STA 780+75.59 SB STA 750+19.70 TO STA 780+75.59 NB IL RTE 16 STA 922+02.0 TO STA 924+67.0 1000-2A	ROADWAY FAU 8239 - URBAN PORTLAND CEMENT CONCRETE RECONSTRUCTION STA 690+15.7 TO STA 750+20.0 NB J000-2A	ROADWAY FAS 1767 - RURAL BITUMINOUS RESURFACING STA 780+75.59 TO STA 842+76.49 BK STA 843+89.12 AH TO STA 981+68.70 1000-2A	ROADWAY FAS 1766 - RURAL BITUMINOUS RESURFACING STA 981+68.70 TO STA 1010+89.70 BK STA 1025+03.03 AH TO STA 1297+00.00 BK STA 50+00.00 AH TO STA 76+72.05 BK STA 109+00.00 AH TO STA 120+90.00 IL RTE 138 - STA 112+63.04 TO STA 124+47.17 1000-2A	ROADWAY SBI 16 - RURAL BITUMINOUS RESURFACING STA 60+90.71 TO STA 40+00 BK STA 1136+96.28 AH TO STA 1176+35.97 BK STA 70+00.00 AH TO STA 64+53.12 1000-2A	TRAFFIC SIGNALS FAS 1766 - RURAL OLD US 66 & IL ROUTE 138 Y031-IF	
20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	18							18	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	20						20		
20200100	EARTH EXCAVATION	CU YD	13,466						13,466		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	1,261				59		1,202		
20800150	TRENCH BACKFILL	CU YD	39		1	6			28	4	
21400100	GRADING AND SHAPING DITCHES	FOOT	21,555		3,087	300	6,037		3,813	8,318	
25000200	SEEDING, CLASS 2	ACRE	15.75		2.25	0.25	4.25		4.50	4.50	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,489		194	24	391		466	414	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	1,489		194	24	391		466	414	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,489		194	24	391		466	414	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	33.1		4.3	0.5	8.7		10.4	9.2	
25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	1.00				0.25		0.75		
25100115	MULCH, METHOD 2	ACRE	16.75		2.25	0.25	4.50		5.25	4.50	
25100630	EROSION CONTROL BLANKET	SO YD	238						238		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5,025		675	75	1,350		1,575	1,350	
28000300	TEMPORARY DITCH CHECKS	EACH	85		10	4	8		28	35	
28000400	PERIMETER EROSION BARRIER	FOOT	2,234		104				2,130		
28000500	INLET AND PIPE PROTECTION	EACH	53		12		9		13	19	
28100208	STONE RIPRAP, CLASS A4 (SPECIAL)	TON	67						67		
28100707	STONE DUMPED RIPRAP, CLASS A4	SO YD	516						516		
28200200	FILTER FABRIC	SO YD	516						516		
30200650	PROCESSING MODIFIED SOIL 12"	SO YD	18,283			18,283					
30201500	LIME	TON	292.5			292.5					
31200100	STABILIZED SUB-BASE, 4"	SO YD	17,642			17,642					
35800100	PREPARATION OF BASE	SO YD	242				242				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	53		2		5		35	11	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	179.2		28.8	0.5	48.4		87.6	13.9	
40600300	AGGREGATE (PRIME COAT)	TON	944		152	2	255		461	74	
40600895	CONSTRUCTING TEST STRIP	EACH	2						2		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD	5,563		1,197	591	610		2,504	661	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	2,537				609		1,760	168	
40600990	TEMPORARY RAMP	SO YD	1,821		892	64	156		628	81	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	447		3		119		206	119	
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SO YD	16,362			16,362					
42001300	PROTECTIVE COAT	SO YD	17,995			16,362			1,633		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 2/8/2006

DRAWN BY TJD
CHECKED BY AWM