RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	RS, R	••	302	5
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

• FAU 8239, FAS 1767, FAS 1766 & SBI 16 (OLD US 66)
•• MONTGOMERY & MACOUPIN COUNTIES

CONTRACT NO. 72526

CODED NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				MONTGOMERY COUNTY				MACOUPIN COUNTY		
			80% FEDERAL 20% STATE	TRAFFIC SIGNALS FAU 8239 - URBAN OLD US 66 & IL ROUTE 16	ROADWAY FAU 8239 - URBAN BITUMINOUS RESURFACING NORTH PROJECT LIMITS TO STA 688+28.13 BK NB & SB STA 688+48.07 AH TO STA 690+15.7 NB & SB STA 690+15.7 TO STA 780+75.59 SB STA 750+19.70 TO STA 780+75.59 NB IL RTE 16 STA 922+02.0 TO STA 924+67.0	ROADWAY FAU 8239 - URBAN PORTLAND CEMENT CONCRETE RECONSTRUCTION STA 690+15.7 TO STA 750+20.0 NB	ROADWAY FAS 1767 - RURAL BITUMINOUS RESURFACING STA 780+75.59 TO STA 842+76.49 BK STA 843+89.12 AH TO STA 981+68.70	ROADWAY FAS 1766 - RURAL BITUMINOUS RESURFACING STA 981+68.70 TO STA 1010+89.70 BK STA 1025+03.03 AH TO STA 1297+00.00 BK STA 50+00.00 AH TO STA 76+72.05 BK STA 109+00.00 AH TO STA 120+90.00 IL RTE 138 - STA 112+63.04 TO STA 124+47.17	ROADWAY SBI 16 - RURAL BITUMINOUS RESURFACING STA 60+90.71 TO STA 40+00 BK STA 1136+96.28 AH TO STA 1176+35.97 BK STA 70+00.00 AH TO STA 64+53.12	TRAFFIC SIGNALS FAS 1766 - RURAL OLD US 66 & IL ROUTE 138
				Y031 - 1F	1000-2A	J000-2A	1000-2A	1000-2A	1000-2A	Y031-1F
54200673	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 48"	FOOT	68					68		
54213669	PRE-CAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	EACH	5					1	4	
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS, 24"	EACH	5		1	1		3		
54248515	CONCRETE COLLAR	EACH	16		2		3	7	4	
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV, 12"	FOOT	36					36		
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV, 18"	FOOT	90					90		
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV, 24"	FOOT	40					40		
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 12"	FOOT	380					380		
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III, 24"	FOOT	114					114		
⊙ 55038200	STORM SEWER TO BE CLEANED 24"	FOOT	1,212					1,212		
55100500	STORM SEWER REMOVAL, 12"	FOOT	40					40		
55100900	STORM SEWER REMOVAL, 18"	FOOT	90					90		
55101100	STORM SEWER REMOVAL, 21"	FOOT	115					115		
55101200	STORM SEWER REMOVAL, 24"	FOOT	46					46		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1					1		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3					3		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2					2		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1					1		
60255500	MANHOLES TO BE ADJUSTED	EACH	1				1			
60500040	REMOVING MANHOLES	EACH	4					4		
60500060	REMOVING INLETS	EACH	2					2		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	7.3					7.3		
60602500	CONCRETE GUTTER, TYPE A	FOOT	1,577.0					1,577.0		
60605000	COMBINATION CONCRETE CURB AND GUTTER, B-6.24	FOOT	354.0					354.0		
60608600	COMBINATION CONCRETE CURB AND GUTTER, M-6.06	FOOT	713.0					713.0		
60618300	CONCRETE MEDIAN SURFACE, 4"	SQ FT	3,079					3,079		
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SQ FT	1,825					1,825		
60624600	CORRUGATED MEDIAN	SQ FT	586					586		
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	762.5					762.5		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	6					6		
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	1,027					1,027		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7		0.5	0.5	2.5	3.0	0.5	

⊙ 100% STATE
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 2/8/2006

DRAWN BY TJD
CHECKED BY AWM

2280-10001