RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	RS, R	**	302	9
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

* FAU 8239, FAS 1767, FAS 1766 & SBI 16 (OLD US 66)
** MONTGOMERY & MACOUPIN COUNTIES

CONTRACT NO. 72526

SEEDING

STATION TO STATION	SIDE	SEEDING, CLASS 2	SEEDING, CLASS 4B (MODIFIED)	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
		ACRE		POUND			TON	ACRE
FAU 8239 - BITUMINOUS RESURFACING - MONTGOMERY COUNTY								
700+00 TO 701+31	RT	0.10		9.0	9.0	9.0	0.20	0.10
714+44 TO 718+00	MEDIAN	0.17		15.3	15.3	15.3	0.34	0.17
717+00 TO 718+15	RT	0.11		9.9	9.9	9.9	0.22	0.11
718+78 TO 722+00	MEDIAN	0.16		14.4	14.4	14.4	0.32	0.16
742+00 TO 744+50	RT	0.14		12.6	12.6	12.6	0.28	0.14
745+39 TO 762+00	RT	1.11		99.9	99.9	99.9	2.22	1.11
746+00 TO 755+00	MEDIAN	0.36		32.4	32.4	32.4	0.72	0.36
FAU 8239 BITUMINOUS SUBTOTALS		2.15		193.50	193.50	193.50	4.30	2.15
FAU 8239 - PCC RECONSTRUCTION - MONTGOMERY COUNTY								
719+00 TO 722+00	LT	0.27		24.3	24.3	24.3	0.54	0.27
FAU 8239 PCC RECONSTRUCTION SUBTOTALS		0.27		24.30	24.30	24.30	0.54	0.27
FAS 1767 - BITUMINOUS RESURFACING - MONTGOMERY COUNTY								
840+00 TO 846+00	RT	0.39		35.1	35.1	35.1	0.78	0.39
849+00 TO 860+50	RT	0.97		87.3	87.3	87.3	1.94	0.97
865+00 TO 867+00	RT	0.16		14.4	14.4	14.4	0.32	0.16
870+25 TO 878+00	RT	0.52		46.8	46.8	46.8	1.04	0.52
886+00 TO 890+00	RT	0.26		23.4	23.4	23.4	0.52	0.26
891+72 TO 909+00	RT	1.15		103.5	103.5	103.5	2.30	1.15
924+00 TO 928+00	RT	0.26		23.4	23.4	23.4	0.52	0.26
932+00 TO 934+00	RT	0.13		11.7	11.7	11.7	0.26	0.13
941+00 TO 943+00	RT	0.20		18.0	18.0	18.0	0.40	0.20
970+00 TO 972+00	RT	0.13		11.7	11.7	11.7	0.26	0.13
979+00 TO 981+50	RT		0.17	15.3	15.3	15.3	0.34	0.17
FAS 1767 SUBTOTALS		4.17	0.17	390.60	390.60	390.60	8.68	4.34
FAS 1766 - BITUMINOUS RESURFACING - MACOUPIN COUNTY								
988+52 TO 996+00	RT		0.50	45.0	45.0	45.0	1.00	0.50
998+00 TO 1000+09	RT		0.14	12.6	12.6	12.6	0.28	0.14
1004+00 TO 1006+00	RT	0.13		11.7	11.7	11.7	0.26	0.13
1007+00 TO 1030+40	RT	0.62		55.8	55.8	55.8	1.24	0.62
1032+30 TO 1039+00	RT	0.44		39.6	39.6	39.6	0.88	0.44
1042+20 TO 1049+30	RT	0.21		18.9	18.9	18.9	0.42	0.21
1044+05 TO 1045+85	LT	0.10		9.0	9.0	9.0	0.20	0.10
1066+00 TO 1071+00	RT	0.33		29.7	29.7	29.7	0.66	0.33
1077+00 TO 1080+00	RT	0.20		18.0	18.0	18.0	0.40	0.20
1193+79 TO 1194+50	LT	0.08		7.2	7.2	7.2	0.16	0.08
1214+00 TO 1215+30	LT	0.07		6.3	6.3	6.3	0.14	0.07
1296+00 TO 52+25	LT	0.18		16.2	16.2	16.2	0.36	0.18
53+15 TO 56+25	LT	0.31		27.9	27.9	27.9	0.62	0.31
56+25 TO 60+24	LT	0.27		24.3	24.3	24.3	0.54	0.27
58+00 TO 61+20	RT	0.03		2.7	2.7	2.7	0.06	0.03
61+50 TO 69+50	LT	0.30		27.0	27.0	27.0	0.60	0.30
62+45 TO 65+34	RT	0.06		5.4	5.4	5.4	0.12	0.06
116+00 TO 118+00	LT	0.11		9.9	9.9	9.9	0.22	0.11
IL ROUTE 138								
111+32 TO 112+82	LT	0.18		16.2	16.2	16.2	0.36	0.18
112+07 TO 112+64	RT	0.06		5.4	5.4	5.4	0.12	0.06
113+23 TO 113+95	LT	0.16		14.4	14.4	14.4	0.32	0.16
113+27 TO 113+90	RT	0.12		10.8	10.8	10.8	0.24	0.12
114+95 TO 116+42	LT	0.21		18.9	18.9	18.9	0.42	0.21
115+16 TO 116+52	RT	0.11		9.9	9.9	9.9	0.22	0.11
118+00 TO 122+00	RT	0.26		23.4	23.4	23.4	0.52	0.26
FAS 1766 SUBTOTALS		4.54	0.64	466.20	466.20	466.20	10.36	5.18
SBI 16 - BITUMINOUS RESURFACING - MACOUPIN COUNTY								
60+42 TO 59+44	LT	0.19		17.1	17.1	17.1	0.38	0.19
58+74 TO 54+00	LT	0.35		31.5	31.5	31.5	0.70	0.35
48+00 TO 43+00	RT	0.93		83.7	83.7	83.7	1.86	0.93
47+50 TO 44+50	LT	0.54		48.6	48.6	48.6	1.08	0.54
1137+00 TO 1140+50	RT	0.13		11.7	11.7	11.7	0.26	0.13
1137+00 TO 1145+35	LT	0.28		25.2	25.2	25.2	0.56	0.28
1142+50 TO 1146+00	RT	0.12		10.8	10.8	10.8	0.24	0.12
1145+97 TO 1148+50	LT	0.09		8.1	8.1	8.1	0.18	0.09
1150+50 TO 1153+42	RT	0.11		9.9	9.9	9.9	0.22	0.11
1150+50 TO 1153+98	LT	0.11		9.9	9.9	9.9	0.22	0.11
HERMAN ROAD	LT	0.08		7.2	7.2	7.2	0.16	0.08
1154+19 TO 1155+50	RT	0.06		5.4	5.4	5.4	0.12	0.06
1154+63 TO 1156+90	LT	0.08		7.2	7.2	7.2	0.16	0.08
1157+25 TO 1160+37	LT	0.10		9.0	9.0	9.0	0.20	0.10
1160+58 TO 1161+00	LT	0.01		0.9	0.9	0.9	0.02	0.01
1161+50 TO 1173+50	RT	0.41		36.9	36.9	36.9	0.82	0.41
1162+37 TO 1171+47	LT	0.31		27.9	27.9	27.9	0.62	0.31
1171+70 TO 1176+00	LT	0.14		12.6	12.6	12.6	0.28	0.14
1173+72 TO 1176+00	RT	0.08		7.2	7.2	7.2	0.16	0.08
70+00 TO 69+17	RT	0.04		3.6	3.6	3.6	0.08	0.04
68+95 TO 64+61	RT	0.25		22.5	22.5	22.5	0.50	0.25
67+50 TO 64+18	LT	0.19		17.1	17.1	17.1	0.38	0.19
SBI 16 SUBTOTALS		4.60		414.00	414.00	414.00	9.20	4.60
TOTALS		15.73	0.81	1488.60	1488.60	1488.60	33.08	16.54
USE		15.75	1.00	1489	1489	1489	33.1	16.75

STONE DUMPED RIPRAP, CLASS A4 & FILTER FABRIC FOR USE WITH RIPRAP

STATION TO STATION	FILTER FABRIC FOR USE WITH RIPRAP	STONE DUMPED RIPRAP CLASS A4
	SQ YD	
FAS 1766 BITUMINOUS RESURFACING - MACOUPIN COUNTY		
1110+21.62 TO 1110+66.80	63.7	63.7
1150+35.66 TO 1150+83.08	104.8	104.8
1176+02.48 TO 1177+42.50	225.2	225.2
1205+67.28 TO 1205+77.28	33.3	33.3
1253+12.64 TO 1253+41.71	45.3	45.3
53+60.11 TO 54+12.79	43.0	43.0
FAS 1766 SUBTOTAL	515.3	515.3
USE	516	516

STONE RIPRAP, CLASS A4 (SPECIAL)

STATION TO STATION	STONE RIPRAP CLASS A4 (SPECIAL)
	TONS
FAS 1766 BITUMINOUS RESURFACING - MACOUPIN COUNTY	
1155+28 TO 1156+73	66.7
FAS 1766 SUBTOTAL	66.7
USE	67

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH

STATION TO STATION		SIDE	WIDTH	LENGTH	AREA
			FT		SQ FT
FAS 1766 - BITUMINOUS RESURFACING - MACOUPIN COUNTY					
60+25.0	61+50.1	LT	VAR.	125.1	839.2
61+20.0	62+44.9	RT	VAR.	124.9	622.3
FAS 1766 SUBTOTAL					1461.5
USE					1462

MODIFIED SOIL, 12"

STATION TO STATION	LENGTH	WIDTH	AREA	PROCESSING MODIFIED SOIL, 12"	LIME
	FT		SQ FT	SQ YD	TON
FAU 8239 PCC RECONSTRUCTION - MONTGOMERY COUNTY					
690+15.70 TO 695+53.49	537.8	27.0	15,058.1	1,613.4	25.8
695+61.99 TO 699+39.57	377.6	27.0	10,572.2	1,132.7	18.1
699+39.57 TO 700+00.17	60.6	24.0	1,454.4	161.6	2.6
700+00.17 TO 713+71.81	1,371.6	27.0	38,405.9	4,114.9	65.8
713+71.81 TO 714+58.37	86.6	24.0	2,077.4	230.8	3.7
TYLER STREET (LT) & CROSSOVER (LT&RT)				409.1	6.5
714+58.37 TO 718+02.25	343.9	27.0	9,628.6	1,031.6	16.5
718+02.25 TO 718+94.46	92.2	24.0	2,213.0	245.9	3.9
718+94.46 TO 744+39.58	2,545.1	27.0	71,263.4	7,635.4	122.2
744+39.58 TO 745+39.10	99.5	24.0	2,388.5	265.4	4.3
745+39.10 TO 750+19.70	480.6	27.0	13,456.8	1,441.8	23.1
FAU 8239 - PCC RECONSTRUCTION SUBTOTAL				18,282.6	292.5
USE				18,283	292.5

NOTE: LIME SHALL BE APPLIED IN A SLURRY ACCORDING TO THE SPECIAL PROVISION FOR SOIL MODIFICATION. THIS WORK SHALL BE PERFORMED BETWEEN WAY 1 AND OCTOBER 1.

STABILIZED SUB-BASE, 4"

STATION TO STATION	LENGTH	WIDTH	AREA	SQ YD
	FT		SQ FT	
FAU 8239 PCC RECONSTRUCTION - MONTGOMERY COUNTY				
690+15.70 TO 695+53.49	537.8	26	13,982.5	1,553.6
695+61.99 TO 699+39.57	377.6	26	9,817.1	1,090.8
699+39.57 TO 700+00.17	60.6	24	1,454.4	161.6
700+00.17 TO 713+71.81	1,371.6	26	35,662.6	3,962.5
713+71.81 TO 714+58.37	86.6	24	2,077.4	230.8
TYLER STREET (LT) & CROSSOVER (LT&RT)				396.9
714+58.37 TO 718+02.25	343.9	26	8,940.9	993.4
718+02.25 TO 718+94.46	92.2	24	2,213.0	245.9
718+94.46 TO 744+39.58	2,545.1	26	66,173.1	7,352.6
744+39.58 TO 745+39.10	99.5	24	2,388.5	265.4
745+39.10 TO 750+19.70	480.6	26	12,495.6	1,388.4
FAU 8239 PCC RECONSTRUCTION SUBTOTAL				17,641.9
USE				17,642

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 2/8/2006

DRAWN BY TJD
CHECKED BY AWM

2280-10002