F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1767	RS, R	•	302	204
STA. 885+00		TO STA. 890+00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• MACOUPIN & MONTGOMERY COUNTIES

CONTRACT NO. 72526

FINAL SURVEY	NOTE BOOK	NO.	BY	DATE
SURVEYED				
PLOTTED				
TYPING DATE				
AREAS				
AREAS CHECKED				

ORIGINAL SURVEY	NOTE BOOK	NO.	BY	DATE
SURVEYED				
PLOTTED				
TYPING DATE				
AREAS				
AREAS CHECKED				

30 20 10 0 10 20 30 40 50 60 70 80 90 100

680 / 675

890+00

END SP. DT. RT.
STA. 890+00.00
GRADE = -0.12%
ELEV. 673.91

1.46% -1.50%

SD 673.91

889+00

SD 674.02

1.50% -1.50%

888+00

BEGIN SP. DT. RT.
STA. 888+00.00
GRADE = -0.12%
ELEV. 674.14

SD 674.14

END SP. DT. RT.
STA. 888+00.00
GRADE = -0.13%
ELEV. 674.14

887+00

SD 674.27

886+00

BEGIN SP. DT. RT.
STA. 886+00.00
GRADE = -0.13%
ELEV. 674.40

SD 674.40

885+00

30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120

THE AGGREGATE SHOULDER ON THE LEFT SIDE SHALL BE 2' WIDE AS SHOWN IN THE TYPICAL SECTIONS RATHER THAN 3' WIDE AS IT IS SHOWN ON THIS SHEET.

OLD ROUTE 66 STA. 885+00 TO STA. 890+00