

**CONTRACT NO. 72680**

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
			80% FEDERAL 20% STATE	ROADWAY 1000 -2A	WETLAND MITIGATION Y077	CULVERT STA 960+46.00 X028 -2A	BRIDGE SEC 34-4B STA 973+28.00 X081-2A	BRIDGE SEC 34-4B-1 STA 1153+07.72 X071 -2A	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E	
20100110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER )	UNIT	1,298	1,298							
20100210	TREE REMOVAL ( OVER 15 UNITS DIAMETER )	UNIT	1,709	1,709							
20100500	TREE REMOVAL, ACRES	ACRE	9.25	9.25							
20200100	EARTH EXCAVATION	CU YD	639,979	615,323	24,656						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,580	3,580							
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	3,660	3,660							
20300100	CHANNEL EXCAVATION	CU YD	3,020				3,020				
20400800	FURNISHED EXCAVATION	CU YD	99,846	99,846							
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	580				470	110			
20800150	TRENCH BACKFILL	CU YD	6,878	6,878							
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	57,196	49,789	7,407						
* 25000200	SEEDING, CLASS 2	ACRE	115	115							
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11,212	10,276	936						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11,212	10,276	936						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11,212	10,276	936						
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	249.8	229.0	20.8						
Δ 25000750	MOWING	ACRE	35.1	20	15.1						
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	10.4		10.4						
* 25003200	INTERSEEDING, CLASS 2	ACRE	20	20							
* 25100115	MULCH, METHOD 2	ACRE	125.4	115	10.4						
* 25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	23,717	23,717							
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	500	500							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	45,000	45,000							

Δ NON-PARTICIPATING  
\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 315  
SUMMARY OF QUANTITIES

DATE 1/31/06  
DRAWN BY TJD  
CHECKED BY JRB