

CONTRACT NO. 72680

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
			80% FEDERAL 20% STATE	ROADWAY I000 - 2A	WETLAND MITIGATION Y077	CULVERT STA 960+46.00 X028 - 2A	BRIDGE SEC 34-4B STA 973+28.00 X081 - 2A	BRIDGE SEC 34-4B-1 STA 1153+07.72 X071 - 2A	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1						
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1				
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1					1			
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1		1						
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1		1						
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1		1						
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1		1						
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	EACH	1		1						
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9	EACH	1		1						
50101200	REMOVAL OF EXISTING STRUCTURES NO. 10	EACH	1		1						
50105210	REMOVE EXISTING CULVERTS	FOOT	2,501		2,501						
50200100	STRUCTURE EXCAVATION	CU YD	1,271					560	711		
50300100	FLOOR DRAINS	EACH	56						56		
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	44						44		
50300160	NEOPRENE EXPANSION JOINT 4"	FOOT	44						44		
50300225	CONCRETE STRUCTURES	CU YD	516.1					90.5	425.6		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	929.8					333.4	596.4		
50300260	BRIDGE DECK GROOVING	SQ YD	2,755					828	1,927		
50300300	PROTECTIVE COAT	SQ YD	3,466					1,034	2,432		
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14						14		
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	21						21		
50300330	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	7						7		
50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN.	FOOT	1,346					1,346			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 315
SUMMARY OF QUANTITIES

DRAWN BY TJD
CHECKED BY JRB

DATE 1/31/06