

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
			80% FEDERAL 20% STATE	ROADWAY I000 - 2A	WETLAND MITIGATION Y077	CULVERT STA 960+46.00 X028 - 2A	BRIDGE SEC 34-4B STA 973+28.00 X081 - 2A	BRIDGE SEC 34-4B-1 STA 1153+07.72 X071 - 2A	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING Y030-1E
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1						1	
50500505	STUD SHEAR CONNECTORS	EACH	7,504						7,504	
50800105	REINFORCEMENT BARS	POUND	15,961	381			15,580			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	237,370				66,210	171,160		
51201100	FURNISHING METAL PILE SHELLS 14"	FOOT	3,879					3,879		
51201600	FURNISHING STEEL PILES HP12X53	FOOT	4,093				2,321	1,772		
51202600	DRIVING AND FILLING SHELLS	FOOT	3,879					3,879		
51202700	DRIVING STEEL PILES	FOOT	4,093				2,321	1,772		
51203200	TEST PILE METAL SHELLS	EACH	2					2		
51203600	TEST PILE STEEL HP12X53	EACH	5				4	1		
51204315	CONCRETE ENCASEMENT	CU YD	52.2					52.2		
51205200	TEMPORARY SHEET PILING	SQ FT	1,079				1,079			
51500100	NAME PLATES	EACH	4			1	2	1		
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2						
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2						
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	1	1						
54001005	BOX CULVERT END SECTION, CULVERT NO. 5	EACH	2	2						
54001006	BOX CULVERT END SECTION, CULVERT NO. 6	EACH	2	2						
54002020	EXPANSION BOLT 3/4 INCH	EACH	14	14						
54003000	CONCRETE BOX CULVERTS	CU YD	98.8			98.8				
54010406	PRECAST CONCRETE BOX CULVERT 4'X6'	FOOT	78.0	78.0						
54010503	PRECAST CONCRETE BOX CULVERT 5'X3'	FOOT	90.0	90.0						

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 315
SUMMARY OF QUANTITIES

DATE 1/31/06

DRAWN BY TJD
CHECKED BY JRB